					DEPARTMENT	T OF N	<b>OF UTAH</b> ATURAL RES , GAS AND I		3		AMEN	FO IDED REPO	RM 3		
		APP	LICATION FO	OR	PERMIT TO DRIL	.L				1. WELL NAME and		<b>R</b> 2-36C4BS			
2. TYPE	OF WORK	RILL NEW WELL (I	REENTER	P&/	A WELL DEEP	EN WEL	т(			3. FIELD OR WILDO		L BUTTES			
4. TYPE	OF WELL	Gas	Well Co	alhe	ed Methane Well: NO		5. UNIT or COMMUNITIZATION AGREEMENT NAME NATURAL BUTTES								
6. NAME	OF OPERATOR	<b>R</b>					7. OPERATOR PHONE 720 929-6515								
8. ADDR	ESS OF OPERA		RR-MCGEE OIL	& G	AS ONSHORE, L.P.					9. OPERATOR E-MA		9-6515			
10 MTNI	RAL LEASE N		P.O. Box 173779	9, De	enver, CO, 80217 <b>11. MINERAL OWN</b>	FDCHTI	D			julie.ja		anadarko	.com		
	L, INDIAN, OF				-	DIAN (	STATE (	FEE			DIAN (	STATE		FEE 💮	
13. NAM	E OF SURFACE	OWNER (if box 1	L2 = 'fee')							14. SURFACE OWN	ER PHO	NE (if box	12 = 'fe	e')	
15. ADD	RESS OF SURF	ACE OWNER (if b	ox 12 = 'fee')	_						16. SURFACE OWN	ER E-MA	IL (if box	12 = 'fe	ee')	
				_	18. INTEND TO CO	MMTNC	LE BRODUCT	TON EDO	м	19. SLANT					
	AN ALLOTTEE 2 = 'INDIAN')	OR TRIBE NAME			MULTIPLE FORMAT	IONS			-			_		_	
					YES (Submit	Commir	ngling Applicat	ion) NO	<u> </u>	VERTICAL DIF	RECTION	AL 📵	HORIZON	ITAL ()	
20. LOC	ATION OF WE	LL		FO	OTAGES	Q	TR-QTR	SECT	TION	TOWNSHIP	R	ANGE	ME	RIDIAN	
LOCATI	ON AT SURFAC	CE	706	FNL	_ 1749 FWL		NENW	30	6	9.0 S	2	2.0 E		S	
Top of l	Jppermost Pro	ducing Zone	746	FNL	_ 2153 FWL		NENW	30	6	9.0 S	2	2.0 E		S	
At Tota	Depth		746	FNL	_ 2153 FWL		NENW	30	6	9.0 S	2	2.0 E		S	
21. COU	NTY	UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 746				23. NUMBER OF ACRES IN DRILLING UNIT 640						
					25. DISTANCE TO N (Applied For Drillin			SAME POO	DL	26. PROPOSED DEF		T) (D, 00)			
27 515	ATTON CROI	IND LEVEL		_		3	362			MD: 8940 TVD: 8907					
27. ELEV	ATION - GROU	5096			28. BOND NUMBER		)13542			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Permit #43-8496					
					Hole, Casing,	, and (	Cement Inf	ormatio	n						
String	Hole Size	Casing Size			ight Grade & T		_			Cement	Sacks	Yield	Weight		
Surf	11	8.625	0 - 2640	28	8.0 J-55 LT	I&C	0.2		Type V Class G			180 270	1.15	15.8 15.8	
Prod	7.875	4.5	0 - 8940	1:	1.6 I-80 LT	Γ&C	12.5 Prer		Premium Lite High Strength		ngth	300	3.38	11.0	
										50/50 Poz 1180 1.31 1					
					A	TTACI	HMENTS								
	VERIFY T	HE FOLLOWIN	G ARE ATTA	СНІ	ED IN ACCORDAN	NCE W	ITH THE U	TAH OIL	. AND (	GAS CONSERVATI	ON GE	NERAL F	RULES		
<b>⊮</b> w	ELL PLAT OR	MAP PREPARED E	Y LICENSED S	UR	VEYOR OR ENGINEE	ER .	<b>I</b> ✓ COM	IPLETE DE	RILLING	G PLAN					
AF	FIDAVIT OF S	TATUS OF SURFA	CE OWNER AG	GREI	EMENT (IF FEE SUR	FACE)	FORI	м 5. IF OF	PERATO	R IS OTHER THAN T	HE LEAS	SE OWNER	1		
DI DRILLED		URVEY PLAN (IF	DIRECTIONAL	LY (	OR HORIZONTALLY		г торо	OGRAPHIO	CAL MA	P					
NAME G	ina Becker			TI	I <b>TLE</b> Regulatory Analy	/st II			PHON	<b>E</b> 720 929-6086					
SIGNAT	URE			D	ATE 05/13/2011				EMAII	gina.becker@anadar	ko.com				
	mber assign 04751614(			AI	PPROVAL				Di	00.64/JU					
									Perr	nit Manager					

NBU 922-36C Pad Drilling Program
1 of 4

## Kerr-McGee Oil & Gas Onshore, L.P.

## NBU 922-36C4BS

Surface: 706 FNL / 1749 FWL NENW BHL: 746 FNL / 2153 FWL NENW

Section 36 T9S R22E

Unitah County, Utah Mineral Lease: ML-22650

## **ONSHORE ORDER NO. 1**

## **DRILLING PROGRAM**

## 1. & 2. <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1350	
Birds Nest	1652	Water
Mahogany	2008	Water
Wasatch	4466	Gas
Mesaverde	6680	Gas
MVU2	7651	Gas
MVL1	8256	Gas
TVD	8907	
TD	8940	

## 3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Drilling Program

## 4. <u>Proposed Casing & Cementing Program:</u>

Please refer to the attached Drilling Program

## 5. <u>Drilling Fluids Program</u>:

Please refer to the attached Drilling Program

## 6. <u>Evaluation Program</u>:

Please refer to the attached Drilling Program

NBU 922-36C Pad Drilling Program 2 of 4

#### 7. Abnormal Conditions:

Maximum anticipated bottom hole pressure calculated at 8907' TVD, approximately equals 5,879 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,728 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

#### **8.** Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

#### 9. <u>Variances:</u>

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

## Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

NBU 922-36C Pad Drilling Program
3 of 4

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

## Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

## Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

## Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 922-36C Pad Drilling Program 4 of 4

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

## Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

## **Other Information:**


Please refer to the attached Drilling Program.

5/6/2011



# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE May 6, 2011 NBU 922-36C4BS WELL NAME TD 8,907'  $\mathsf{TVD}$ 8,940' MD **FIELD** Natural Buttes **COUNTY** Uintah STATE Utah FINISHED ELEVATION 5096.1 SURFACE LOCATION NENW 706 FNL 1749 FWL Sec 36 T 9S R 22E Latitude: 39.997876 Longitude: -109.390809 NAD 27 BTM HOLE LOCATION NENW 746 FNL 2153 FWL Sec 36 T 9S R 22E Latitude: 39.997763 -109.389367 NAD 27 Longitude: OBJECTIVE ZONE(S) Wasatch/Mesaverde





## KERR-McGEE OIL & GAS ONSHORE LP

**DRILLING PROGRAM** 

CASING PROGRAM	<u>1</u>								DESIGN I	ACTORS	
										LTC	BTC
	SIZE	INT	ERVAL		WT.	GR.	CPLG.	BURST	COLLA	PSE	TENSION
CONDUCTOR	14"	(	)-40'								
								3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0	to	2,460	28.00	IJ-55	LTC	2.20	1.63	5.77	N/A
								7,780	6,350	279,000	367,000
PRODUCTION	4-1/2"	0	to	8,940	11.60	I-80	LTC/BTC	1.11	1.10	3.33	4.37

**Surface Casing:** 

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### **CEMENT PROGRAM**

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1		+ 0.25 pps flocele				
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
		+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to	o surface,	option 2 wil	l be utilized	
Option 2 LEAD	1,960'	65/35 Poz + 6% Gel + 10 pps gilsonite	180	35%	11.00	3.82
		+ 0.25 pps Flocele + 3% salt BWOW				
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
		+ 0.25 pps flocele				
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION LEAD	3,960'	Premium Lite II +0.25 pps	300	20%	11.00	3.38
		celloflake + 5 pps gilsonite + 10% gel				
		+ 0.5% extender				
TAIL	4,980'	50/50 Poz/G + 10% salt + 2% gel	1,180	35%	14.30	1.31
		+ 0.1% R-3				

<sup>\*</sup>Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

#### **FLOAT EQUIPMENT & CENTRALIZERS**

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

## ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.


BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.	
Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.	


DRILLING ENGINEER:		DATE:	
	Nick Spence / Emile Goodwin		
DRILLING SUPERINTENDENT:		DATE:	
	Kenny Gathings / Lovel Young		

<sup>\*</sup>Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained


EXHIBIT A NBU 922-36C4BS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



			SU	RFACE POS	SITION							R	OTTO	M HOLE			
WELL NAME	NAD83			NAD27						D83			NAI	D27			
NIDILI	<b>LATITUDE LONGITUDE</b> 39°59'52.286" 109°23'29.469"				LATITUDE LONGITUDE			FOOTAG		ITUDE		GITUDE		TITUDE	LONGI		FOOTAGES
NBU 922-36C1CS	39°59'52.28 39.997857°	6" 109°23'29  109.39151		39°59'52. 39.997892		109°23'27 109.3908		700' FNI 1741' FW	-	'54.402" 8445°	109°23 109.39	3'24.189" 0052°	1	9'54.526" 98479°	109°23'2 109.3893		485' FNL 2152' FWL
NBU	39°59'52.22	8" 109°23'29	.365"	39°59'52.	.352"	109°23'26	6.913"	706' FNI	L 39°59	51.823"	109°23	3'24.174"	39°59	9'51.947"	109°23'2	21.722"	746' FNL
922-36C4BS NBU	39.997841° 39°59'52.16	9" 109.39149 9" 109°23'29		39.997870 39°59'52.		109.3908 109°23'26		1749' FW 712' FNI			109.39	0048° 3'24.206"		97763° 9'42.146"	109.3893 109°23'2		2153' FWL 1738' FNL
922-36F1CS	39.997825°	109.39146		39.997859		109.3907		1757' FW			109.39			95041°	109.3893		2150' FWL
NBU 922-36F1BS	39°59'52.11 39.997809°	1" 109°23'29 109.39143		39°59'52. 39.997843		109°23'26 109.3907.		718' FNI 1765' FW	-		109°23 109.39	3'24.195"	1	9'45.417" 95949°			1407' FNL 2151' FWL
NBU 922-36C	39°59'52.05				_	109.3907.		724' FNI		7713	109.39	0034	133.33	73777	109.3893	3/3	ZIJI FVVL
	39.997792°	109.39140	)4°	39.997826	6°	109.3907	<sup>7</sup> 23°	1773' FW	/L								
			II=		т —				face Positic								
WELL NAME NBU	NORTH	EAST	NBU	LL NAME		ORTH	EAS	NIDI	ELL NAME U	NOR		EAST		VELL NAM BU		ORTH	EAST
922-36C1CS	214.5	410.8		2-36C4BS	4	40.6'	404.		2-36F1CS	-1,02	26.7'	394.4	11	22-36F1BS	s -68	89.8'	386.91
<u></u>																	
										\				_			
												•					
									$\rightarrow$	<del></del>	′ /						
									/ .	3411	, AA'						
				\ \					62.1	45 46	5//						
									AV 03	どし	lole)						
DACIC OF	DE A DINICC I	C THE WIFE	T I IN!	E .				~6	AZ=62.4 7080	ittom'		.09		30'	<u>.</u> 0		.09
		S THE WEST TION 36, T				`		/ /	LOBE	<i>,</i> -							
		TAKEN FRO		44L,				X .							- A		
		IG SATELLIT		D 4 4			$\times$	\ /	/					5 (	CALE		
OBSERVAT	FIONS TO E	BEAR N00°0	4'40"	"W.	10.	,/		$\sqrt{}$	<b>(</b>								
				, 6	$\langle \rangle$	10,10,											
					5	<del>/-&gt;</del> -			_			Az=	=95.7	<sup>7</sup> 4167°			
					१८	ZO ST	VICT	ING W	— — - Ell:	- 1		-UOR	Otto				
				33.00	05	ბ∖ ( <sup>©\ E.</sup>		IIAO M	CLL:		• 0	0 404 -	. —	: ",			
			-	7. C. A.	5 ひこ	, / / <b>/</b> /	JRII	977 266			13	04°15'	30"E	- 406	15'	_	_
			્રં		300	, / / <b>N</b>	1BU S	922-360 `				84°15'	'30"E	- 406.	15'	_	
		_	80 %		), ,,,,,,,,,	, / , N	/ 1BN 8	922-360 `\				04°15'	'30"E	- 406.	15'	_	
		· //:	18 S.		Y'SKY		/ /BD 8	922-360	C	ĵ., \		104°15'	'30"E	- 406.	15'	_	
		20 % (1) % (	SON SON	SASON SASON	N'S	' \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	IBU 9	922-360	C	(3° ×		104°15'	'30"E	- 406.	15'		
			20 14 1.00 %	SAN	1,30 1,30 1,41		1BU 9	<b>922-360</b>	C	)3° / 26.29°		104°15'	'30"E	- 406.	15'		
			Se 50 1 18 19 19 19 19 19 19 19 19 19 19 19 19 19	AND SOLVE	3,00	, \\ <b>N</b>	1BU 9	922-360	C	53° \\ 26.23 \\ 290 \\		104°15'	'30"E	- 406.	15'		
	.>		59.50, 100 .05.05.05.05.05.05.05.05.05.05.05.05.05.	A SOLO SOLO SOLO SOLO SOLO SOLO SOLO SOL	N. S.	, \\ <b>N</b>	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA	53. \ 26.290 \		104°15'	'30"E	- 406.	15'		
	4,		29, 65, 50, 18. 18. 18. 18. 18. 18. 18. 18. 18. 18.	N. S.	y's A	, \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	15'		
			19 19 10 00 00 00 00 00 00 00 00 00 00 00 00	NA STAN		, \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	) 		
			1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1	A STANTON	, , , , , , , , , , , , , , , , , , ,	, (10, VI)	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	15'		
			18 18 18 18 18 18 18 18 18 18 18 18 18 1	N. S.	100	N (10 158:	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	15'		
		10 60 15 15 15 15 15 15 15 15 15 15 15 15 15	10 10 00 00 00 00 00 00 00 00 00 00 00 0	NA STAN	S. A.	N (10 k) 58.90°	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	15'		
	A A A A A A A A A A A A A A A A A A A	September 19 Septe	(6) (4) (1) (5) (5) (5) (5) (5) (5) (5) (5) (5) (5	NA STAN		N (10 h) 58.90°	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	15'		
		10 60 14 14 14 15 10 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	70° 50° 50° 50° 50° 50° 50° 50° 50° 50° 5	NA STAN	330	N (TO V 58.900)	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	15'		
		1, 1, 2, 2, 1, 1, 1, 1, 2, 2, 3, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1,	10 50 50 50 50 50 50 50 50 50 50 50 50 50	NO STANCE OF STA	3,33	N (10 k) 58.90°	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ASS			104°15'	'30"E	- 406.	15'	<b>\</b>	
	A A A A A A A A A A A A A A A A A A A	10 6 6 6 7 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10 % 65 65 65 65 65 65 65 65 65 65 65 65 65	NO STANCE	3.00	AZ=158.90°	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	30"E	- 406.	15'		
	A ST	Constitution of the state of th	10 00 00 00 00 00 00 00 00 00 00 00 00 0	NO STAN	3,33	N (10 k) 58.900	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	15'		
	10 5 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Constitution of the state of th	(A) (1) (2) (8) (8) (1) (1) (1) (1) (1) (1) (1) (1) (1) (1	NO STANDAR		N (TO V 58.900	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	15'		
	A A A A A A A A A A A A A A A A A A A	Constitution of the state of th	10 50 50 50 50 50 50 50 50 50 50 50 50 50	NO STANDARY OF STA	1	AZ=158.90°	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	'30"E	- 406.	15'		<b>-</b>
	A A A A A A A A A A A A A A A A A A A	Control of the contro	10 % 10 % 10 % 10 % 10 % 10 % 10 % 10 %	NO STANCE	1	NZ=158.900	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		C ARIA			104°15'	30"E	- 406.	15'		
Kerr-Mc0	4		\		\	N (10 b) 58.900	·		C ARIA			104°15'	'30"E	- 406.	15'		
Kerr-Mc0	Gee Oil		Ons	shore, I	\	NZ=158.900	·		C ARIA			104°15'	30"E	- 406.	15'		
Kerr-Mc(	Gee Oil 8th Street - I	& Gas (	Ons	shore, L 80202	\	N (10 0 158.900	·		C	11528°	14 15 6°°	04*15	'30"E		15'	<b>N</b>	35) 789-1365
Kerr-Mc(	Gee Oil 8th Street - I	& Gas (	Ons	shore, L 80202	\	N (10 p) 58.900	·	S29°17'099.87'	C	115280	IMB	BERL	130"E		SURVE		
Kerr-Mc( 1099 13 WEL	Gee Oil 8th Street - I L PAD -	& Gas (	Onsorado	shore, I 80202 36C	\	N (10 b) 58.900	·	S29°17'099.87'	C	7528	IMB ENGIN 2091	BERLINEERIN NORTH 3	130"E	E		YING	i, INC.
Kerr-McC 1099 18 WEL WELL I WELLS - NB	Gee Oil Bith Street - I L PAD - PAD INT BU 922-36	& Gas (Denver, Color NBU 9) ERFERENCICS, NBU	Ons orado 22-3 NCE U 92	shore, L 80202 36C PLAT 22-36C4B	LP		S21°00'47"E Hole) S21°00'47"E Hole) S21°00'47"E Hole) S21°00'47"E Hole)	529°17'099.87' 609 ULTING,	C	TI DAT	IMB ENGIN 2091	BERLINEERIN NORTH 3	130"E	E	SURVE RNAL, UT	YING TAH 840	78
Kerr-McC 1099 18 WEL WELL I WELLS - NB NBU 92	Gee Oil Bth Street - I L PAD - PAD INT BU 922-36 12-36F1CS	& Gas (Denver, Color NBU 92) FERFEREN C1CS, NBU 92	Ons 22-: NCE U 92 222-30	shore, I 80202 36C PLAT 22-36C4B 6F1BS,	LP	C 21	S21°00'47"E" Hole)  S21°00'47"E" Hole)  S21°00'47"E" Hole)  S21°00'47"E" Hole)	\$29°.17°.	C Street CO Street	DAT 08-3	IMB ENGIN 2091	BERLI NEERIN NORTH :	130"E	E LAND est - vef urveyed e	SURVE RNAL, UT BY: M.S.B.	YING TAH 840	i, INC. 078
WELL I WELLS - NB NBU 92 LOCAT	Gee Oil Bth Street - I L PAD - PAD INT SU 922-36 12-36F1CS ED IN SEC	& Gas (Denver, Color NBU 9) ERFERENCICS, NBU	Ons 22-: NCE U 92 222-30 T9S,	shore, L 80202 36C PLAT 22-36C4B 6F1BS, R22E,	LP	C 21	S21°00'47"E Hole) S21°00'47"E Hole) S21°00'47"E Solomon Hole) S21°00'47"E Solomon Hole) S21°00'47"E Hole) S21°00'47"E Hole)	529°17'099.87' 609 ULTING,	To Bottom Ho. 100.90	DAT 08-3 DAT	IMB ENGIN 2091 E SURVE	BERLI NEERIN NORTH :	130"E	E LAND EST - VER	SURVE RNAL, UT BY: M.S.B. : B.M.	YING TAH 840	i, INC.






PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE






PHOTO VIEW: FROM EXISTING ACCESS ROAD

**CAMERA ANGLE: NORTHEASTERLY** 

## Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

## WELL PAD - NBU 922-36C

LOCATION PHOTOS
NBU 922-36C1CS, NBU 922-36C4BS,
NBU 922-36F1CS & NBU 922-36F1BS
LOCATED IN SECTION 36, T9S, R22E,
S.L.B.&M., UINTAH COUNTY, UTAH.



## CONSULTING, LLC 2155 North Main Street

2155 North Main Street Sheridan WY 82801 Phone 307-674-0609 Fax 307-674-0182

## TIMBERLINE


(435) 789-1365


SHEET NO:


9 OF 16


ENGINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078


DATE PHOTOS TAKEN: 08-30-10	PHOTOS TAKEN BY: M.S.B.
DATE DRAWN: 11-15-10	DRAWN BY: B.M.
Date Last Revised:	














# Kerr-McGee Oil & Gas Onshore, LP WELL PAD – NBU 922-36C WELLS – NBU 922-36C1CS, NBU 922-36C4BS, NBU 922-36F1CS & NBU 922-36F1BS Section 36, T9S, R22E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East Street in Vernal, Utah, proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 14.4 miles to the intersection of the Fidlar Road (County B Road 3410) which road intersection is approximately 400 feet northeast of the Mountain Fuel Bridge at the White River. Exit left and proceed in a southeasterly direction along the Fidlar Road approximately 4.4 miles to the intersection of the Seven Sisters Road (County B Road 3420). Exit right and proceed in a southerly, then southeasterly direction along the Seven Sisters Road approximately 1.2 miles to a Class D County Road to the southwest. Exit right and proceed in a southwesterly, then southerly direction along the Class D County Road approximately 0.5 miles to a second Class D County Road to the west. Exit right and proceed in a westerly, then northwesterly direction along the second Class D County Road approximately 0.8 miles to a service road to the south. Exit left and proceed in a southerly direction along the service road approximately 0.6 miles to a proposed service road re-route to the east. Exit left and follow road flags in an easterly direction approximately 475 feet to an existing access road to the northeast. Exit left and proceed in a northeasterly direction approximately 0.1 miles to the proposed well pad.

Total distance from Vernal, Utah to the proposed well location is approximately 45.6 miles in a southerly direction.

**SHEET 16 OF 16** 

API Well Number: 430475161400@oject: Uintah County, UT UTM12 Scientific Drilling


Site: NBU 922-36C PAD


Well: NBU 922-36C4BS


Wellbore: OH

Design: PLAN #1 2-7-11 RHS











# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36C PAD NBU 922-36C4BS

ОН

Plan: PLAN #1 2-7-11 RHS

# **Standard Planning Report**

07 February, 2011





# **SDI**Planning Report



Database: EDM5000-RobertS-Local

Company: Kerr McGee Oil and Gas Onshore LP

 Project:
 Uintah County, UT UTM12

 Site:
 NBU 922-36C PAD

 Well:
 NBU 922-36C4BS

Wellbore: OH

Design: PLAN #1 2-7-11 RHS

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

**Survey Calculation Method:** 

Well NBU 922-36C4BS

GL 5096 & KB 4 @ 5100.00ft (ASSUMED) GL 5096 & KB 4 @ 5100.00ft (ASSUMED)

True

Minimum Curvature

Project Uintah County, UT UTM12

Map System: Universal Transverse Mercator (US Survey Feet)

 Geo Datum:
 NAD 1927 - Western US

 Map Zone:
 Zone 12N (114 W to 108 W)

System Datum: Mean Sea Level

Site NBU 922-36C PAD, SECTION 36 T9S R22E

Northing: 14,529,345.24 usft Site Position: Latitude: 39° 59' 52.411 N From: Lat/Long Easting: 2,091,100.13 usft Longitude: 109° 23' 27.017 W **Position Uncertainty:** 0.00 ft Slot Radius: **Grid Convergence:** 1.03 13.200 in

Well NBU 922-36C4BS, 706 FNL 1749 FWL

 Well Position
 +N/-S
 -5.83 ft
 Northing:
 14,529,339.56 usft
 Latitude:
 39° 59' 52.354 N

 +E/-W
 8.12 ft
 Easting:
 2,091,108.35 usft
 Longitude:
 109° 23' 26.912 W

Position Uncertainty 0.00 ft Wellhead Elevation: Ground Level: 5,096.00 ft

Wellbore ОН Magnetics **Model Name** Sample Date Declination Dip Angle Field Strength (nT) (°) (°) IGRF2010 02/07/2011 11.07 65.90 52,377

PLAN #1 2-7-11 RHS Design **Audit Notes:** Version: Phase: PLAN Tie On Depth: 0.00 **Vertical Section:** Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 95.82

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
800.00	10.00	95.82	797.47	-4.41	43.30	2.00	2.00	0.00	95.82	
2,601.23	10.00	95.82	2,571.33	-36.11	354.47	0.00	0.00	0.00	0.00	
3,172.66	0.00	0.00	3,139.86	-41.15	403.95	1.75	-1.75	0.00	180.00	
8,939.80	0.00	0.00	8,907.00	-41.15	403.95	0.00	0.00	0.00	0.00	PBHL_NBU 922-36C



# **SDI**Planning Report



Database: Company:

Project:

Site:

EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12 NBU 922-36C PAD

Well: NBU 922-36C4BS

Wellbore: OH

Design: PLAN #1 2-7-11 RHS

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well NBU 922-36C4BS

GL 5096 & KB 4 @ 5100.00ft (ASSUMED) GL 5096 & KB 4 @ 5100.00ft (ASSUMED)

True

Minimum Curvature

Design:	PLAN #1 2-7-	11 RHS							
Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.0		0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.0		0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.0		0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Bui	ld 2.00								
400.0		95.82	399.98	-0.18	1.74	1.75	2.00	2.00	0.00
500.0	00 4.00	95.82	499.84	-0.71	6.94	6.98	2.00	2.00	0.00
600.0		95.82	599.45	-1.59	15.61	15.69	2.00	2.00	0.00
700.0		95.82	698.70	-2.83	27.74	27.88	2.00	2.00	0.00
800.0		95.82	797.47	-4.41	43.30	43.52	2.00	2.00	0.00
Start 180	1.23 hold at 800.00	MD							
900.0	00 10.00	95.82	895.95	-6.17	60.57	60.89	0.00	0.00	0.00
1,000.0	00 10.00	95.82	994.43	-7.93	77.85	78.25	0.00	0.00	0.00
1,100.0		95.82	1,092.91	-9.69	95.12	95.62	0.00	0.00	0.00
1,200.0		95.82	1,191.39	-11.45	112.40	112.98	0.00	0.00	0.00
1,300.0	00 10.00	95.82	1,289.87	-13.21	129.68	130.35	0.00	0.00	0.00
1,361.0	10.00	95.82	1,350.00	-14.29	140.22	140.95	0.00	0.00	0.00
WASATC	H								
1,400.0	00 10.00	95.82	1,388.35	-14.97	146.95	147.71	0.00	0.00	0.00
1,500.0		95.82	1,486.83	-16.73	164.23	165.08	0.00	0.00	0.00
1,600.0	00 10.00	95.82	1,585.31	-18.49	181.50	182.44	0.00	0.00	0.00
1,700.0	00 10.00	95.82	1,683.79	-20.25	198.78	199.81	0.00	0.00	0.00
1,800.0	00 10.00	95.82	1,782.27	-22.01	216.05	217.17	0.00	0.00	0.00
1,900.0	00 10.00	95.82	1,880.75	-23.77	233.33	234.54	0.00	0.00	0.00
2,000.0	00 10.00	95.82	1,979.23	-25.53	250.60	251.90	0.00	0.00	0.00
2,100.0		95.82	2,077.72	-27.29	267.88	269.27	0.00	0.00	0.00
2,200.0		95.82	2,176.20	-29.05	285.15	286.63	0.00	0.00	0.00
2,300.0	00 10.00	95.82	2,274.68	-30.81	302.43	303.99	0.00	0.00	0.00
2,400.0	00 10.00	95.82	2,373.16	-32.57	319.70	321.36	0.00	0.00	0.00
2,486.1	5 10.00	95.82	2,458.00	-34.09	334.59	336.32	0.00	0.00	0.00
8 5/8"									
2,500.0		95.82	2,471.64	-34.33	336.98	338.72	0.00	0.00	0.00
2,600.0		95.82	2,570.12	-36.09	354.26	356.09	0.00	0.00	0.00
2,601.2		95.82	2,571.33	-36.11	354.47	356.30	0.00	0.00	0.00
Start Dro	p -1.75								
2,700.0	00 8.27	95.82	2,668.84	-37.70	370.07	371.98	1.75	-1.75	0.00
2,800.0		95.82	2,768.01	-39.01	382.88	384.86	1.75	-1.75	0.00
2,900.0		95.82	2,867.52	-40.00	392.66	394.70	1.75	-1.75	0.00
3,000.0		95.82	2,967.28	-40.69	399.42	401.49	1.75	-1.75	0.00
3,100.0	00 1.27	95.82	3,067.21	-41.07	403.15	405.24	1.75	-1.75	0.00
3,172.6		0.00	3,139.86	-41.15	403.95	406.04	1.75	-1.75	0.00
	7.14 hold at 3172.66								
3,200.0		0.00	3,167.20	-41.15	403.95	406.04	0.00	0.00	0.00
3,300.0		0.00	3,267.20	-41.15	403.95	406.04	0.00	0.00	0.00
3,400.0 3,500.0		0.00 0.00	3,367.20 3,467.20	-41.15 -41.15	403.95 403.95	406.04 406.04	0.00 0.00	0.00 0.00	0.00 0.00
3,600.0		0.00	3,567.20	-41.15	403.95	406.04	0.00	0.00	0.00
3,700.0		0.00	3,667.20	-41.15	403.95	406.04	0.00	0.00	0.00
3,800.0 3,900.0		0.00 0.00	3,767.20 3,867.20	-41.15 -41.15	403.95 403.95	406.04 406.04	0.00 0.00	0.00 0.00	0.00 0.00
4,000.0		0.00	3,967.20	-41.15 -41.15	403.95	406.04	0.00	0.00	0.00
4,100.0		0.00	4,067.20	-41.15	403.95	406.04	0.00	0.00	0.00
4,200.0	0.00	0.00	4,167.20	-41.15	403.95	406.04	0.00	0.00	0.00



## SDI **Planning Report**



Database: Company: Project:

EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

Uintah County, UT UTM12 NBU 922-36C PAD

Site: Well: NBU 922-36C4BS

Wellbore: ОН Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well NBU 922-36C4BS

GL 5096 & KB 4 @ 5100.00ft (ASSUMED) GL 5096 & KB 4 @ 5100.00ft (ASSUMED)

True

Minimum Curvature

Design:	PLAN #1 2-7-	11 RHS							
Planned Survey									
Measured Depth	lu alimatia n	A =:	Vertical Depth	+N/-S	+E/-W	Vertical Section	Dogleg Rate	Build Rate	Turn Rate
(ft)	Inclination (°)	Azimuth (°)	(ft)	+N/-S (ft)	+⊑/-VV (ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)
4,300.00		0.00	4,267.20	-41.15	403.95	406.04	0.00	0.00	0.00
4,400.00 4,498.80		0.00 0.00	4,367.20 4,466.00	-41.15 -41.15	403.95 403.95	406.04 406.04	0.00 0.00	0.00 0.00	0.00 0.00
GREEN RI		0.00	1, 100.00		.00.00		0.00	0.00	0.00
4,500.00	0.00	0.00	4,467.20	-41.15	403.95	406.04	0.00	0.00	0.00
4,600.00		0.00	4,567.20	-41.15	403.95	406.04	0.00	0.00	0.00
4,700.00		0.00	4,667.20	-41.15	403.95	406.04	0.00	0.00	0.00
4,800.00		0.00	4,767.20	-41.15	403.95	406.04	0.00	0.00	0.00
4,900.00	0.00	0.00	4,867.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,000.00		0.00	4,967.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,100.00		0.00	5,067.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,200.00		0.00	5,167.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,300.00		0.00	5,267.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,400.00	0.00	0.00	5,367.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,500.00		0.00	5,467.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,600.00		0.00	5,567.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,700.00		0.00	5,667.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,800.00		0.00	5,767.20	-41.15	403.95	406.04	0.00	0.00	0.00
5,900.00	0.00	0.00	5,867.20	-41.15	403.95	406.04	0.00	0.00	0.00
6,000.00		0.00	5,967.20	-41.15	403.95	406.04	0.00	0.00	0.00
6,100.00		0.00	6,067.20	-41.15	403.95	406.04	0.00	0.00	0.00
6,200.00		0.00	6,167.20	-41.15	403.95	406.04	0.00	0.00	0.00
6,300.00		0.00	6,267.20	-41.15	403.95	406.04	0.00	0.00	0.00
6,400.00	0.00	0.00	6,367.20	-41.15	403.95	406.04	0.00	0.00	0.00
6,500.00		0.00	6,467.20	-41.15	403.95	406.04	0.00	0.00	0.00
6,600.00		0.00	6,567.20	-41.15	403.95	406.04	0.00	0.00	0.00
6,700.00		0.00	6,667.20	-41.15	403.95	406.04	0.00	0.00	0.00
6,712.80		0.00	6,680.00	-41.15	403.95	406.04	0.00	0.00	0.00
MESAVER 6,800.00		0.00	6,767.20	-41.15	403.95	406.04	0.00	0.00	0.00
,									
6,900.00		0.00	6,867.20	-41.15	403.95	406.04	0.00	0.00	0.00
7,000.00		0.00	6,967.20	-41.15	403.95	406.04	0.00	0.00	0.00
7,100.00		0.00	7,067.20	-41.15	403.95	406.04	0.00	0.00	0.00
7,200.00 7,300.00		0.00 0.00	7,167.20 7,267.20	-41.15 -41.15	403.95 403.95	406.04 406.04	0.00 0.00	0.00 0.00	0.00 0.00
			*						
7,400.00		0.00	7,367.20	-41.15	403.95	406.04	0.00	0.00	0.00
7,500.00		0.00	7,467.20	-41.15	403.95	406.04	0.00	0.00	0.00
7,600.00		0.00	7,567.20	-41.15	403.95	406.04	0.00	0.00	0.00
7,700.00 7,800.00		0.00 0.00	7,667.20 7,767.20	-41.15 -41.15	403.95 403.95	406.04 406.04	0.00 0.00	0.00 0.00	0.00 0.00
,									
7,900.00		0.00	7,867.20	-41.15	403.95	406.04	0.00	0.00	0.00
8,000.00		0.00	7,967.20	-41.15	403.95	406.04	0.00	0.00	0.00
8,100.00		0.00	8,067.20	-41.15	403.95	406.04	0.00	0.00	0.00
8,200.00 8,300.00		0.00 0.00	8,167.20 8,267.20	-41.15 -41.15	403.95 403.95	406.04 406.04	0.00 0.00	0.00 0.00	0.00
									0.00
8,400.00		0.00	8,367.20	-41.15	403.95	406.04	0.00	0.00	0.00
8,500.00		0.00	8,467.20	-41.15	403.95	406.04	0.00	0.00	0.00
8,600.00		0.00	8,567.20	-41.15	403.95	406.04	0.00	0.00	0.00
8,700.00		0.00	8,667.20	-41.15	403.95	406.04	0.00	0.00	0.00
8,800.00		0.00	8,767.20	-41.15	403.95	406.04	0.00	0.00	0.00
8,900.00		0.00	8,867.20	-41.15	403.95	406.04	0.00	0.00	0.00
8,939.80		0.00	8,907.00	-41.15	403.95	406.04	0.00	0.00	0.00
TD at 8939	.80 - PBHL_NBU 9	922-36C4BS							



## SDI **Planning Report**



Database: Company: EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12 NBU 922-36C PAD Site:

Well: NBU 922-36C4BS ОН

Wellbore:

Design: PLAN #1 2-7-11 RHS Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well NBU 922-36C4BS

GL 5096 & KB 4 @ 5100.00ft (ASSUMED) GL 5096 & KB 4 @ 5100.00ft (ASSUMED)

True

Minimum Curvature

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 922-36C4B! - plan hits target cen - Circle (radius 25.00		0.00	8,907.00	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59′ 51.947 N	109° 23' 21.721 W

Casing Points							
	Measured	Vertical			Casing	Hole	
	Depth	Depth			Diameter	Diameter	
	(ft)	(ft)		Name	(in)	(in)	
	2,486.15	2,458.00	8 5/8"		8.625	11.000	

Formations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,361.06	1,350.00	WASATCH				
	4,498.80	4,466.00	GREEN RIVER				
	6,712.80	6,680.00	MESAVERDE				

Plan Annotations				
Measured	Vertical	Local Coor	dinates	
Depth	Depth	+N/-S	+E/-W	
(ft)	(ft)	(ft)	(ft)	Comment
300.00	300.00	0.00	0.00	Start Build 2.00
800.00	797.47	-4.41	43.30	Start 1801.23 hold at 800.00 MD
2,601.23	2,571.33	-36.11	354.47	Start Drop -1.75
3,172.66	3,139.86	-41.15	403.95	Start 5767.14 hold at 3172.66 MD
8,939.80	8,907.00	-41.15	403.95	TD at 8939.80



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36C PAD NBU 922-36C4BS

OH

Plan: PLAN #1 2-7-11 RHS

# **Standard Planning Report - Geographic**

07 February, 2011





## SDI Planning Report - Geographic



EDM5000-RobertS-Local Database: Company:

Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12 NBU 922-36C PAD Site: Well: NBU 922-36C4BS

Wellbore: ОН

PLAN #1 2-7-11 RHS Design:

**Local Co-ordinate Reference:** 

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well NBU 922-36C4BS

GL 5096 & KB 4 @ 5100.00ft (ASSUMED) GL 5096 & KB 4 @ 5100.00ft (ASSUMED)

True

Minimum Curvature

Project Uintah County, UT UTM12

Map System: Universal Transverse Mercator (US Survey Feet)

NAD 1927 - Western US

System Datum:

Mean Sea Level

Geo Datum: Map Zone: Zone 12N (114 W to 108 W)

NBU 922-36C PAD, SECTION 36 T9S R22E Site

14,529,345.24 usft Northing: Site Position: Latitude: 39° 59' 52.411 N 2,091,100.13 usft 109° 23' 27.017 W Lat/Long Easting: From: Longitude: Position Uncertainty: 0.00 ft Slot Radius: 13.200 in **Grid Convergence:** 1.03 9

Well NBU 922-36C4BS, 706 FNL 1749 FWL

**Well Position** +N/-S 0.00 ft Northing: 14,529,339.56 usft Latitude: 39° 59' 52.354 N +E/-W 0.00 ft Easting: 2,091,108.35 usft Longitude: 109° 23' 26.912 W

Wellhead Elevation: **Position Uncertainty** 0.00 ft **Ground Level:** 5,096.00 ft

ОН Wellbore Magnetics **Model Name** Sample Date Declination Dip Angle Field Strength (°) (°) (nT) 65.90 IGRF2010 02/07/2011 11.07 52,377

PLAN #1 2-7-11 RHS Design **Audit Notes:** Version: Phase: PLAN Tie On Depth: 0.00 **Vertical Section:** Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 95.82

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
800.00	10.00	95.82	797.47	-4.41	43.30	2.00	2.00	0.00	95.82	
2,601.23	10.00	95.82	2,571.33	-36.11	354.47	0.00	0.00	0.00	0.00	
3,172.66	0.00	0.00	3,139.86	-41.15	403.95	1.75	-1.75	0.00	180.00	
8,939.80	0.00	0.00	8,907.00	-41.15	403.95	0.00	0.00	0.00	0.00 F	BHL_NBU 922-36C



# SDI Planning Report - Geographic



EDM5000-RobertS-Local Database:

Kerr McGee Oil and Gas Onshore LP

Company: Project: Uintah County, UT UTM12 NBU 922-36C PAD Site:

NBU 922-36C4BS

Wellbore: ОН

Well:

Design: PLAN #1 2-7-11 RHS Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well NBU 922-36C4BS

GL 5096 & KB 4 @ 5100.00ft (ASSUMED) GL 5096 & KB 4 @ 5100.00ft (ASSUMED)

True

Minimum Curvature

Plar	ned Survey									
	Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
										_
	0.00	0.00	0.00	0.00	0.00	0.00	14,529,339.56	2,091,108.35	39° 59' 52.354 N	109° 23' 26.912 W
	100.00	0.00	0.00	100.00	0.00	0.00	14,529,339.56	2,091,108.35	39° 59' 52.354 N	109° 23' 26.912 W
	200.00	0.00	0.00	200.00	0.00	0.00	14,529,339.56	2,091,108.35	39° 59' 52.354 N	109° 23' 26.912 W
	300.00	0.00	0.00	300.00	0.00	0.00	14,529,339.56	2,091,108.35	39° 59' 52.354 N	109° 23' 26.912 W
	Start Bui		05.00	200.00	0.40	4 74	44 500 220 42	0.004.440.00	20° 501 50 250 N	400% 001 00 000 141
	400.00	2.00	95.82	399.98	-0.18	1.74	14,529,339.42	2,091,110.09	39° 59' 52.352 N	109° 23' 26.890 W
	500.00	4.00	95.82	499.84	-0.71	6.94	14,529,338.98	2,091,115.31	39° 59' 52.347 N	109° 23' 26.823 W
	600.00	6.00	95.82	599.45	-1.59	15.61	14,529,338.25	2,091,123.99	39° 59' 52.338 N	109° 23' 26.712 W
	700.00 800.00	8.00 10.00	95.82 95.82	698.70	-2.83	27.74	14,529,337.24	2,091,136.14	39° 59' 52.326 N	109° 23' 26.556 W
				797.47	-4.41	43.30	14,529,335.93	2,091,151.72	39° 59' 52.310 N	109° 23' 26.356 W
		1.23 hold at 8		905.05	6 17	60.57	14 520 224 40	2 004 460 02	20° E0' E2 202 N	100° 22' 26 124 W
	900.00	10.00	95.82 95.82	895.95 994.43	-6.17 -7.93	60.57	14,529,334.49	2,091,169.03	39° 59' 52.293 N	109° 23' 26.134 W 109° 23' 25.912 W
	1,000.00	10.00			-7.93 -9.69	77.85 95.12	14,529,333.04	2,091,186.33	39° 59' 52.275 N	
	1,100.00	10.00	95.82	1,092.91			14,529,331.59	2,091,203.64	39° 59' 52.258 N	109° 23' 25.690 W 109° 23' 25.468 W
	1,200.00	10.00	95.82	1,191.39	-11.45	112.40	14,529,330.14 14,529,328.69	2,091,220.94	39° 59' 52.240 N	109° 23' 25.246 W
	1,300.00 1,361.06	10.00 10.00	95.82 95.82	1,289.87 1,350.00	-13.21 -14.29	129.68 140.22	14,529,326.69	2,091,238.25 2,091,248.81	39° 59' 52.223 N 39° 59' 52.212 N	109° 23' 25.246 W
			95.62	1,350.00	-14.29	140.22	14,529,527.61	2,091,246.61	39 39 32.212 N	109 23 25.110 W
	1,400.00	<b>лн</b> 10.00	95.82	1,388.35	-14.97	146.95	14,529,327.25	2,091,255.55	39° 59' 52.206 N	109° 23' 25.024 W
	1,500.00	10.00	95.82	1,486.83	-14.97	164.23	14,529,327.25	2,091,233.33	39° 59' 52.188 N	109° 23' 24.802 W
	1,600.00	10.00	95.82	1,585.31	-18.49	181.50	14,529,324.35	2,091,272.00	39° 59' 52.171 N	109° 23' 24.580 W
	1,700.00	10.00	95.82	1,683.79	-10.49	198.78	14,529,324.33	2,091,290.16	39° 59' 52.171 N	109° 23' 24.358 W
	1,800.00	10.00	95.82	1,782.27	-20.23	216.05	14,529,321.46	2,091,324.77	39° 59' 52.136 N	109° 23' 24.136 W
	1,900.00	10.00	95.82	1,880.75	-23.77	233.33	14,529,320.01	2,091,342.07	39° 59' 52.119 N	109° 23' 23.914 W
	2,000.00	10.00	95.82	1,979.23	-25.53	250.60	14,529,318.56	2,091,359.38	39° 59' 52.101 N	109° 23' 23.692 W
	2,100.00	10.00	95.82	2,077.72	-27.29	267.88	14,529,317.11	2,091,376.68	39° 59' 52.084 N	109° 23' 23.470 W
	2,200.00	10.00	95.82	2,176.20	-29.05	285.15	14,529,315.66	2,091,393.99	39° 59' 52.066 N	109° 23' 23.248 W
	2,300.00	10.00	95.82	2,274.68	-30.81	302.43	14,529,314.22	2,091,411.29	39° 59' 52.049 N	109° 23' 23.026 W
	2,400.00	10.00	95.82	2,373.16	-32.57	319.70	14,529,312.77	2,091,428.59	39° 59' 52.032 N	109° 23' 22.804 W
	2,486.15	10.00	95.82	2,458.00	-34.09	334.59	14,529,311.52	2,091,443.50	39° 59' 52.017 N	109° 23' 22.613 W
	8 5/8"			,			, ,	, ,		
	2,500.00	10.00	95.82	2,471.64	-34.33	336.98	14,529,311.32	2,091,445.90	39° 59' 52.014 N	109° 23' 22.582 W
	2,600.00	10.00	95.82	2,570.12	-36.09	354.26	14,529,309.87	2,091,463.20	39° 59' 51.997 N	109° 23' 22.360 W
	2,601.23	10.00	95.82	2,571.33	-36.11	354.47	14,529,309.86	2,091,463.42	39° 59' 51.997 N	109° 23' 22.357 W
	Start Dro			,			, ,	, ,		
	2,700.00	8.27	95.82	2,668.84	-37.70	370.07	14,529,308.55	2,091,479.04	39° 59' 51.981 N	109° 23' 22.157 W
	2,800.00	6.52	95.82	2,768.01	-39.01	382.88	14,529,307.47	2,091,491.87	39° 59' 51.968 N	109° 23' 21.992 W
	2,900.00	4.77	95.82	2,867.52	-40.00	392.66	14,529,306.65	2,091,501.67	39° 59' 51.958 N	109° 23' 21.866 W
	3,000.00	3.02	95.82	2,967.28	-40.69	399.42	14,529,306.09	2,091,508.45	39° 59' 51.951 N	109° 23' 21.779 W
	3,100.00	1.27	95.82	3,067.21	-41.07	403.15	14,529,305.78	2,091,512.18	39° 59' 51.948 N	109° 23' 21.732 W
	3,172.66	0.00	0.00	3,139.86	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	Start 576	7.14 hold at 3	172.66 MD							
	3,200.00	0.00	0.00	3,167.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	3,300.00	0.00	0.00	3,267.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	3,400.00	0.00	0.00	3,367.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	3,500.00	0.00	0.00	3,467.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	3,600.00	0.00	0.00	3,567.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	3,700.00	0.00	0.00	3,667.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	3,800.00	0.00	0.00	3,767.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	3,900.00	0.00	0.00	3,867.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	4,000.00	0.00	0.00	3,967.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	4,100.00	0.00	0.00	4,067.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
	4,200.00	0.00	0.00	4,167.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
<u> </u>	4,300.00	0.00	0.00	4,267.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W



## SDI Planning Report - Geographic



EDM5000-RobertS-Local Database: Company:

Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12 NBU 922-36C PAD Site:

Well: NBU 922-36C4BS

Wellbore: ОН

Design: PLAN #1 2-7-11 RHS Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

**Survey Calculation Method:** 

Well NBU 922-36C4BS

GL 5096 & KB 4 @ 5100.00ft (ASSUMED) GL 5096 & KB 4 @ 5100.00ft (ASSUMED)

True

Minimum Curvature

Design:	FLAI	1#12-7-11 R	110						
Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
4,400.00	0.00	0.00	4,367.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
4,498.80	0.00	0.00	4,466.00	-41.15 -41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
GREEN I		0.00	4,400.00	71.10	400.00	14,020,000.71	2,001,012.00	00 00 01.047 14	100 20 21.721 **
4,500.00	0.00	0.00	4,467.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
4,600.00	0.00	0.00	4,567.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
4,700.00	0.00	0.00	4,667.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
4,800.00	0.00	0.00	4,767.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
4,900.00	0.00	0.00	4,867.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,000.00	0.00	0.00	4,967.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,100.00	0.00	0.00	5,067.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,200.00	0.00	0.00	5,167.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,300.00	0.00	0.00	5,267.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,400.00	0.00	0.00	5,367.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,500.00	0.00	0.00	5,467.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,600.00	0.00	0.00	5,567.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,700.00	0.00	0.00	5,667.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,800.00	0.00	0.00	5,767.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
5,900.00 6,000.00	0.00 0.00	0.00 0.00	5,867.20 5.967.20	-41.15 -41.15	403.95 403.95	14,529,305.71 14,529,305.71	2,091,512.98 2,091,512.98	39° 59' 51.947 N 39° 59' 51.947 N	109° 23' 21.721 W 109° 23' 21.721 W
6,100.00	0.00	0.00	6,067.20	-41.15 -41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
6,200.00	0.00	0.00	6,167.20	-41.15 -41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
6,300.00	0.00	0.00	6,267.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
6,400.00	0.00	0.00	6,367.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
6,500.00	0.00	0.00	6,467.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
6,600.00	0.00	0.00	6,567.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
6,700.00	0.00	0.00	6,667.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
6,712.80	0.00	0.00	6,680.00	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
MESAVE	RDE								
6,800.00	0.00	0.00	6,767.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
6,900.00	0.00	0.00	6,867.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
7,000.00	0.00	0.00	6,967.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
7,100.00	0.00	0.00	7,067.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
7,200.00	0.00	0.00	7,167.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
7,300.00	0.00	0.00	7,267.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
7,400.00	0.00	0.00	7,367.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
7,500.00	0.00	0.00 0.00	7,467.20	-41.15 -41.15	403.95 403.95	14,529,305.71 14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
7,600.00 7,700.00	0.00	0.00	7,567.20 7,667.20	-41.15 -41.15	403.95	14,529,305.71	2,091,512.98 2,091,512.98	39° 59' 51.947 N 39° 59' 51.947 N	109° 23' 21.721 W 109° 23' 21.721 W
7,800.00	0.00	0.00	7,767.20	-41.15 -41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
7,900.00	0.00	0.00	7,867.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,000.00	0.00	0.00	7,967.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,100.00	0.00	0.00	8,067.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,200.00	0.00	0.00	8,167.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,300.00	0.00	0.00	8,267.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,400.00	0.00	0.00	8,367.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,500.00	0.00	0.00	8,467.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,600.00	0.00	0.00	8,567.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,700.00	0.00	0.00	8,667.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,800.00	0.00	0.00	8,767.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,900.00	0.00	0.00	8,867.20	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
8,939.80	0.00	0.00	8,907.00	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W
TD at 893	39.80 - PBHL_	NBU 922-360	C4BS						



# **SDI**Planning Report - Geographic



Database: Company: EDM5000-RobertS-Local

Kerr McGee Oil and Gas Onshore LP

Project: Uintah County, UT UTM12
Site: NBU 922-36C PAD

Well: Wellbore:

ОН

Design:

NBU 922-36C4BS OH PLAN #1 2-7-11 RHS Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 922-36C4BS

GL 5096 & KB 4 @ 5100.00ft (ASSUMED) GL 5096 & KB 4 @ 5100.00ft (ASSUMED)

True

Minimum Curvature

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
PBHL_NBU 922-36C4B: - plan hits target cen - Circle (radius 25.00		0.00	8,907.00	-41.15	403.95	14,529,305.71	2,091,512.98	39° 59' 51.947 N	109° 23' 21.721 W

Casing Points						
	Measured	Vertical			Casing	Hole
	Depth	Depth			Diameter	Diameter
	(ft)	(ft)	N:	ame	(in)	(in)
	2,486.15	2,458.00	8 5/8"		8.625	11.000

Formations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,361.06	1,350.00	WASATCH				
	4,498.80	4,466.00	GREEN RIVER				
	6,712.80	6,680.00	MESAVERDE				

Plan Annotations				
Measured	Vertical	Local Coord	dinates	
Depth (ft)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Comment
300.00	300.00	0.00	0.00	Start Build 2.00
800.00	797.47	-4.41	43.30	Start 1801.23 hold at 800.00 MD
2,601.23	2,571.33	-36.11	354.47	Start Drop -1.75
3,172.66	3,139.86	-41.15	403.95	Start 5767.14 hold at 3172.66 MD
8,939.80	8,907.00	-41.15	403.95	TD at 8939.80

## **NBU 922-36C1CS**

Surface: 700' FNL 1741' FWL (NE/4NW/4) BHL: 485' FNL 2152' FWL (NE/4NW/4)

## **NBU 922-36C4BS**

Surface: 706' FNL 1749' FWL (NE/4NW/4) BHL: 746' FNL 2153' FWL (NE/4NW/4)

## **NBU 922-36F1BS**

Surface: 718' FNL 1765' FWL (NE/4NW/4) BHL: 1407' FNL 2151' FWL (SE/4NW/4)

## **NBU 922-36F1CS**

Surface: 712' FNL 1757' FWL (NE/4NW/4) BHL: 1738' FNL 2150' FWL (SE/4NW/4)

> Pad: NBU 922-36C Pad Section 36 T09S R22E Mineral Lease: ML-22650

Uintah County, Utah Operator: Kerr-McGee Oil & Gas Onshore LP

## MULTI-POINT SURFACE USE PLAN of OPERATIONS (SUPO)

This SUPO contains surface operating procedures for Kerr-McGee Oil & Gas Onshore LP (KMG), a wholly owned subsidiary of Anadarko Petroleum Corporation (APC) pertaining to actions that involve the State of Utah School and Institutional Trust Lands Administration (SITLA) in the development of minerals leased to KMG (including, but not limited to, APDs/SULAs/ROEs/ROWs and/or easements).

See associated Utah Division of Oil, Gas, and Mining (UDOGM) Form 3(s), plats, maps, and other attachments for site-specific information on projects represented herein.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

## A. <u>Existing Roads</u>:

Existing roads consist of county roads and improved/unimproved lease roads. KMG will maintain existing roads in a condition that is the same as or better than before operations began and in a safe and usable condition. Maintenance of existing roads will continue until final abandonment and reclamation of well pads and/or other facilities. The road maintenance may include, but is not limited to, blading, ditching, culvert installation/cleanout, surfacing, and dust control.

Typically, roads, gathering lines and electrical distribution lines will occupy common disturbance corridors and roadways will be used as working space. All disturbances located in the same corridor will overlap each

NBU 922-36C1CS / 36C4BS/ 36F1BS/ 36F1CS

Surface Use Plan of Operations Page 2

other to the maximum extent possible; in no case will the maximum disturbance width of the access road and utility corridors exceed 50', unless otherwise approved.

## B. Planned Access Roads:

Since the proposed NBU 922-36D pad will cut into the existing road, a new access road is being proposed (see Topo Map B). The ±475' road re-route will run along the proposed gas and liquid gathering lines between two existing roads, to the Southwest of the pad. Applicable Uintah County encroachment and/or pipeline crossing permits will be obtained prior to construction/development. No other pipelines will be crossed at this location.

If there are roads that are new or to be reconstructed, they will be located, designed, and maintained to meet the standards of SITLA and other commonly accepted Best Management Practices (BMPs). If a new road/corridor were to cross a water of the United States, KMG will adhere to the requirements of applicable Nationwide or Individual Permits of the Department of Army Corps of Engineers.

During the onsite, turnouts, major cut and fills, culverts, bridges, gates, cattle guards, low water crossings, or modifications needed to existing infrastructure/facilities were determined, as applicable, are typically shown on attached Exhibits and Topo maps.

## C. Location of Existing and Proposed Facilities:

This pad will expand the existing pad for the NBU 922-36C. The NBU 922-36C well location is a vertical producing well according to Utah Division of Oil, Gas and Mining (UDOGM) records as of April 13, 2011.

Production facilities (see Well Pad Design Summary and Facilities Diagram):

Production facilities will be installed on the disturbed portion of the well pad and may include bermed components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will be constructed of compacted subsoil or corrugated metal, impervious, designed to hold 110% of the capacity of the largest tank, and be independent of the back cut. All permanent (on-site six months or longer) above ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth-tone color chosen at the onsite in coordination with SITLA.

Production tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks are not to be used for disposal of liquids from additional sources without prior approval of UDOGM.

## **Gathering facilities:**

## NBU 922-36C1CS / 36C4BS/ 36F1BS/ 36F1CS

Surface Use Plan of Operations Page 3

The following pipeline transmission facilities will apply if the well is productive (see Topo D):

The total gas gathering (steel line pipe with fusion bond epoxy coating) pipeline distances from the meter to the tie in point is  $\pm 1,135$ ' and the individual segments are broken up as follows:

- $\pm 85$ ' (0.02 miles) –New 6" buried gas pipeline from the meter to the edge of the pad. Please refer to Topo D2.
- ±130' (0.02 miles) –New 6" buried gas pipeline from the edge of pad to the proposed tie-in at the proposed 16" buried gas pipeline 36D intersection. Please refer to Topo D.
- ±920' (0.2 miles) –New 16" buried gas pipeline from the 36D intersection to the proposed tie-in point at 36B intersection. Please refer to Topo D.

The total liquid gathering pipeline distance from the separator to the tie in point is  $\pm 1,135$ ' and the individual segments are broken up as follows:

- $\pm 85$ ' (0.02 miles) –New 6" buried liquid pipeline from the separator to the edge of the pad. Please refer to Topo D2.
- ±130' (0.02 miles) –New 6" buried liquid pipeline from the edge of pad to the proposed tie-in at the proposed 6" buried liquid pipeline 36D intersection. Please refer to Topo D.
- ±920' (0.2 miles) –New 6" buried liquid pipeline from the 36D intersection to the proposed tie-in point at 36B intersection. Please refer to Topo D.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

The proposed pipelines will be buried and will include gas gathering and liquid gathering pipelines in the same trench. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. KMG requests a permanent 30' right-of-way adjacent to the road for life-of-project for maintenance, repairs, and/or upgrades, no additional right-of-way will be needed beyond the 30'. Where the pipeline is not adjacent to the road or well pad, KMG requests a temporary 45' construction right-of-way and 30' permanent right-of-way.

The proposed trench width for the pipeline would range from 18-48 inches and will be excavated to a depth of 48 to 60 inches of normal soil cover or 24 inches of cover in consolidated rock. During construction blasting may occur along the proposed right-of-way where trenching equipment cannot cut into the bedrock. Large debris and rocks removed from the earth during trenching and blasting that could not be returned to the trench would be distributed evenly and naturally in the project area. The proposed pipelines will be pressure tested pneumatically (depending on size) or with fluids (either fresh or produced). If fluids are used, there will be no discharge to the surface.

NBU 922-36C1CS / 36C4BS/ 36F1BS/ 36F1CS

Surface Use Plan of Operations Page 4

Pipeline signs will be installed along the right-of-way to indicate the pipeline proximity and ownership, as well as to provide emergency contact phone numbers. Above ground valves, T's, and/or cathodic protection will be installed at various locations for connection, corrosion prevention and/or for safety purposes.

## D. <u>Location and Type of Water Supply</u>:

Water for drilling purposes will be obtained from one of the following sources:

- Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.
- Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

## **E.** Source of Construction Materials:

Construction operations will typically be completed with native materials found on location. If needed, construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source and described in subsequent Sundry requests. No construction materials will be removed from State lands without prior approval from SITLA.

## F. <u>Methods of Handling Waste Materials:</u>

Should the well be productive, produced water will be contained in a water tank and will be transported by pipeline and/or truck to an approved disposal sites facilities and/or Salt Water Disposal (SWD) injection well. Currently, those facilities are:

RNI in Sec. 5 T9S R22E

Ace Oilfield in Sec. 2 T6S R20E MC&MC in Sec. 12 T6S R19E Pipeline Facility in Sec. 36 T9S R20E

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

Ouray #1 SWD in Sec. 1 T9S R21E NBU 159 SWD in Sec. 35 T9S R21E CIGE 112D SWD in Sec. 19 T9S R21E CIGE 114 SWD in Sec. 34 T9S R21E NBU 921-34K SWD in Sec. 34 T9S R21E NBU 921-33F SWD in Sec. 33 T9S R21E NBU 921-34L SWD in Sec. 34 T9S R21E

# NBU 922-36C1CS / 36C4BS/ 36F1BS/ 36F1CS

Surface Use Plan of Operations Page 5

Drill cuttings and/or fluids will be contained in the reserve/frac pit. Cuttings will be buried in pit(s) upon closure. Unless otherwise approved, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface runoff. Should fluid hydrocarbons be encountered during drilling, completions or well testing, product will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by SITLA. Should timely removal prove infeasible, the pit will be netted with mesh no larger than 1 inch until such time as hydrocarbons can be removed. Hydrocarbon removal will also take place prior to the closure of the pit, unless authorization is provided for disposal via alternative pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with a synthetic material 20-mil or thicker, The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

For the protection of livestock and wildlife, all open pits and cellars will be fenced/covered to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after six (6) months from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Additional drying methods may include fly-ash solidification or sprinkler evaporation. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift. Reserve pit liners will be cut off or folded as near to the mud surface as possible and as safety considerations allow and buried on location.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the

NBU 922-36C1CS / 36C4BS/ 36F1BS/ 36F1CS

Surface Use Plan of Operations Page 6

contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Any undesirable event, including accidental release of fluids, or release in excess of reportable quantities, will be managed according to the notification requirements of UDOGMs "Reporting Oil and Gas Undesirable Events" rule. Where State wells are participatory to a Federal agreement, according to NTL-3A, the appropriate Federal agencies will be notified.

# **Materials Management**

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities and may be kept in limited quantities on drilling sites and well locations for short periods of time during drilling or completion activities.

# **G.** Ancillary Facilities:

None are anticipated.

# H. Well Site Layout (see Well Pad Design Summary):

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit, access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project where applicable. Site-specific conditions may require slight deviation in actual equipment and facility layout; however, the area of disturbance, as described in the survey, will not be exceeded.

Coordinates are provided in the National Spatial Reference System, North American Datum, 1927 (NAD27) or latest edition. Distances are depicted on each plat to the nearest two adjacent section lines.

# I. Plans for Reclamation of the Surface:

Surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. This reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well

# NBU 922-36C1CS / 36C4BS/ 36F1BS/ 36F1CS

Surface Use Plan of Operations Page 7

plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but are not limited to: re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

#### **Interim Reclamation**

Interim reclamation includes pit closure, re-contouring (where possible), soil bed preparation, topsoil placement, seeding, and/or weed control.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit.

#### **Final Reclamation**

Final reclamation will be performed for newly drilled unproductive wells and/or at the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by KMG. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring, final grading will be conducted over the entire surface of the well site and access road. Where practical, the area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers and surface materials will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep perpendicular to the natural flow of water.

NBU 922-36C1CS / 36C4BS/ 36F1BS/ 36F1CS

Surface Use Plan of Operations Page 8

All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded.

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to UDOGM.

# Seeding and Measures Common to Interim and Final Reclamation

Reclaimed areas may be fenced to exclude grazing and encourage re-vegetation.

On slopes where severe erosion can become a problem and the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. The slope will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to, erosion control blankets and bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Seeding will occur year-round as conditions allow. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for revegetation. The site specific seed mix will be provided by SITLA.

# J. <u>Surface/Mineral Ownership</u>:

SITLA 675 East 500 South, Suite 500 Salt Lake City, UT 84102

# **K.** Other Information:

None

NBU 922-36C1CS / 36C4BS/ 36F1BS/ 36F1CS

Surface Use Plan of Operations

Page 9

# M. Lessee's or Operators' Representative & Certification:

Gina T. Becker Regulatory Analyst II Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6086 Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage for State lease activities is provided by State Surety Bond 22013542, and for applicable Federal lease activities and pursuant to 43 CFR 3104, by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Gina T. Becker

May 12, 2011

Date



JOE JOHNSON LANDMAN KERR-MCGEE ONSHORE OIL & GAS, L.P. 1099 18TH STREET, SUITE 1800, DENVER, CO 80202 720-929-6708 • FAX 720-929-7708

E-MAIL: JOE.JOHNSON@ANADARKO.COM

April 13, 2011

Ms. Diana Mason Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11

NBU 922-36C4BS

T9S-R22E

Section 36: NENW/NENW Surface: 706' FNL, 1749' FWL Bottom Hole: 746' FNL, 2153' FWL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.


- Kerr-McGee's NBU 922-36C4BS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire
  directional well bore.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joseph D. Johnson Landman



# **United States Department of the Interior**

# BUREAU OF LAND MANAGEMENT

Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

May 20, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2011 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Natural Buttes Unit, Uintah County, Utah.

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

# **NBU 922-36I PAD**

BHL Sec 36 T09S R22E 2071 FNL 0494 FEL 43-047-51587 NBU 922-36H4CS Sec 36 T09S R22E 2014 FSL 0792 FEL BHL Sec 36 T09S R22E 2508 FNL 0495 FEL 43-047-51588 NBU 922-36I1CS Sec 36 T09S R22E 2021 FSL 0785 FEL BHL Sec 36 T09S R22E 2237 FSL 0494 FEL 43-047-51589 NBU 922-36I4CS Sec 36 T09S R22E 1999 FSL 0805 FEL BHL Sec 36 T09S R22E 1574 FSL 0493 FEL **NBU 922-36K PAD** 43-047-51590 NBU 922-36K1BS Sec 36 T09S R22E 1798 FSL 1998 FWL BHL Sec 36 T09S R22E 2567 FSL 2148 FWL 43-047-51591 NBU 922-36K1CS Sec 36 T09S R22E 1809 FSL 2015 FWL BHL Sec 36 T09S R22E 2236 FSL 2147 FWL 43-047-51592 NBU 922-36K4BS Sec 36 T09S R22E 1815 FSL 2023 FWL BHL Sec 36 T09S R22E 1904 FSL 2147 FWL 43-047-51593 NBU 922-36K4CS Sec 36 T09S R22E 1804 FSL 2006 FWL BHL Sec 36 T09S R22E 1573 FSL 2146 FWL 43-047-51594 NBU 922-36L4CS Sec 36 T09S R22E 1793 FSL 1990 FWL BHL Sec 36 T09S R22E 1565 FSL 0821 FWL

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE

, 1										
NBU 922-36N PAI	)									
		922-36M1CS	Sec	36	T09S	R22E	1078	FSL	2379	FWL
						R22E				
43-047-51596	NBU	922-36M4CS	Sec	36	T09S	R22E	1068	FSL	2379	FWL
		BHL	Sec	36	T09S	R22E	0132	FSL	0819	FWL
43-047-51597	NBU	922-36N1BS	Sec	36	T09S	R22E	1088	FSL	2379	FWL
		BHL	Sec	36	T09S	R22E	1253	FSL	2140	FWL
43-047-51598	NBU	922-36N4CS	Sec	36	T09S	R22E	1048	FSL	2379	FWL
		BHL	Sec	36	T09S	R22E	0190	FSL	2081	FWL
43-047-51599	NBU	922-3604CS	Sec	36	T09S	R22E	1058	FSL	2379	FWL
		BHL	Sec	36	T09S	R22E	0085	FSL	1814	FEL
NBU 922-360 PAI	D									
43-047-51600	NBU	922-36J1CS	Sec	36	T09S	R22E	1247	FSL	2113	FEL
		BHL	Sec	36	T09S	R22E	2071	FSL	1809	FEL
43-047-51601	NBU	922-36J4BS	Sec	36	T09S	R22E	1254	FSL	2094	FEL
		BHL	Sec	36	T09S	R22E	1740	FSL	1816	FEL
43-047-51602	NBU	922-36J4CS	Sec	36	T09S	R22E	1261	FSL	2075	FEL
		BHL	Sec	36	T09S	R22E	1409	FSL	1816	FEL
43-047-51603	NBU	922-3601BS								
		BHL	Sec	36	T09S	R22E	1078	FSL	1815	FEL
43-047-51604	NBU	922-3604BS								
	_	BHL	Sec	36	T09S	R22E	0415	FSL	1814	FEL
NBU 922-36P PAI		000 00-1-5	_	0.6			1000		0.000	
43-047-51605	NBU	922-36P1BS								
		BHL	Sec	36	T09S	R22E	1243	FSL	0493	F.E.T
10 017 51606		000 0651 00	~	2.6	T000	5005	1100		0.611	
43-047-51606	NBU	922-36P1CS						_		
		BHL	Sec	36	T09S	R22E	0911	FSL	0493	F.E.T
40 047 51607	NIDII	000 265459	0	2.0	m000	DOOF	1100	ПОТ	0.61.6	
43-04/-5160/	NBU	922-36P4BS								
		BHL	sec	36	1095	RZZE	0580	FSL	0493	FEL
42 047 E1C00	NIDII	000 000400	C	20	шоос	DOOR	1101	DOT	0.001	DDI
43-047-51608	NBO	922-36P4CS								
NDU 022 26D DAE	,	BHL	sec	36	1095	KZZŁ	0243	FSL	0492	FLL
NBU 922-36B PAI	_	922-36A1CS	900	36	ሞበበር	DYYE	0670	דואים	2272	CCT
43-047-31609	NDU	922-36AICS BHL								
		DHL	sec	20	1020	rzzľ	0400	ΓИЪ	0494	ىلىء
43-047-51610	MRII	922-36B1CS	500	36	тлас	R22E	0674	EMI	2222	ਸ਼ੁਸ਼ਸ
10 041 01010	יייי	BHL								
		חוום	טפט	50	1000	1 \	0019	T 1/17	1021	עעיי
43-047-51611	NRII	922-36B4BS	Sec	36	тООС	R22F	0682	FMT	2264	FFT.
10 04/ 01011	טעיי	>55 20D4D0	200	20	1000	T/C/C L	0002	T 1/17	1000	

**RECEIVED:** Jul. 26, 2011

BHL Sec 36 T09S R22E 0905 FNL 1828 FEL

Page 3

API # WELL	NAME		]	LOCAT	ION				
(Proposed PZ WAS	ATCH-MESA VERDI	₹.							
43-047-51612 NBU								2291 1861	
<b>NBU 922-36C PAD</b> 43-047-51613 NBU								1741 2152	
43-047-51614 NBU								1749 2153	
43-047-51615 NBU								1765 2151	
43-047-51616 NBU								1757 2150	
<b>NBU 922-36D PAD</b> 43-047-51617 NBU								0981 0825	
43-047-51618 NBU								0971 0825	
43-047-51619 NBU								0990 0825	
43-047-51620 NBU	922-36E1BS BHL								
<b>NBU 922-36E PAD</b> 43-047-51621 NBU	922_36F1CC	500	36	т∩ас	D22F	1692	E'NIT	0730	דואים
43-047-31021 NDO								0824	
43-047-51622 NBU								0729 0818	
43-047-51623 NBU								0719 0824	
43-047-51624 NBU								0709 0824	
NBU 922-36G3 PAD	000 268489	0	2.0	шооа	DOOR	0.41.4	TINIT	0440	
43-047-51625 NBU								2149	
43-047-51626 NBU								2445 2149	
43-047-51627 NBU								2441 1818	
43-047-51628 NBU								2447 1818	

Page 4

This office has no objection to permitting the wells at this time.

Digitally signed by Michael L. Coulthard Michael L. Coulthard

Management, ou=Branch of Minerals, email=Michael\_Coulthard@blm.gov, c=US
Date: 2011.05.23 07:16:05-06'00'

bcc: File - Natural Buttes Unit Division of Oil Gas and Mining

Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:5-20-11

From: Jim Davis

To: Bonner, Ed; Garrison, LaVonne; Hill, Brad; Mason, Diana

CC: Gina Becker; Lytle, Andy Date: 6/8/2011 3:00 PM

**Subject:** Kerr McGee APD approvals.

```
The following APDs have been approved by SITLA including arch and paleo clearance.
```

```
4304751586
             NBU 922-36H4BS
4304751587
             NBU 922-36H4CS
4304751588
             NBU 922-36I1CS
4304751589
             NBU 922-36I4CS
4304751590
             NBU 922-36K1BS
             NBU 922-36K1CS
4304751591
4304751592
             NBU 922-36K4BS
4304751593
             NBU 922-36K4CS
             NBU 922-36L4CS
4304751594
             NBU 922-36M1CS
4304751595
             NBU 922-36M4CS
4304751596
4304751597
             NBU 922-36N1BS
4304751598
             NBU 922-36N4CS
4304751599
             NBU 922-36O4CS
             NBU 922-36J1CS
4304751600
4304751601
             NBU 922-36J4BS
4304751602
             NBU 922-36J4CS
4304751603
             NBU 922-3601BS
4304751604
             NBU 922-36O4BS
4304751605
             NBU 922-36P1BS
4304751606
             NBU 922-36P1CS
4304751607
             NBU 922-36P4BS
             NBU 922-36P4CS
4304751608
4304751613
             NBU 922-36C1CS
             NBU 922-36C4BS
4304751614
4304751615
             NBU 922-36F1BS
4304751616
             NBU 922-36F1CS
4304751617
             NBU 922-36D1CS
4304751618
             NBU 922-36D4BS
4304751619
             NBU 922-36D4CS
4304751620
             NBU 922-36E1BS
4304751621
             NBU 922-36E1CS
4304751622
             NBU 922-36E4BS
4304751623
             NBU 922-36E4CS
4304751624
             NBU 922-36L1BS
4304751625
             NBU 922-36F4BS
4304751626
             NBU 922-36F4CS
4304751627
             NBU 922-36G4BS
4304751628
             NBU 922-36G4CS
```

Full paleo monitoring is a required condition for the approval of these APDs- as recommended in the paleo report.

4304751609 NBU 922-36A1CS 4304751610 NBU 922-36B1CS 4304751611 NBU 922-36B4BS 4304751612 NBU 922-36G1BS

Thanks.

-Jim


Jim Davis Utah Trust Lands Administration jimdavis1@utah.gov Phone: (801) 538-5156

# BOPE REVIEW KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 922-36C4BS 43047516140000

Well Name		KERR-MCGE	E	OIL & GAS ON	SH	IORE, L.P. NI	ВU	922-36C4BS	
String		Surf	Ī	Prod	Г	ĺ	Ī		
Casing Size(")		8.625	Ť	4.500	Ī	i	Ī		
Setting Depth (TVD)		2432	ľ	8907	Ė		Ť		
Previous Shoe Setting Dept	th (TVD)	40	ľ	2432	Ē		Ï	==	
Max Mud Weight (ppg)		8.4	ľ	12.5	Ī		Ī		
BOPE Proposed (psi)		1000	ľ	5000	Ė		ľ	=	
Casing Internal Yield (psi)		3390	ť	7780	Ė		ľ		
Operators Max Anticipated	d Pressure (psi)	5700	H	12.3	Ī		ľ		
			12		1		100		
Calculations	Sur	f String	_	D 140 m		8.62	25	"	
Max BHP (psi)		.052*Settii	ng	g Depth*MW	/=	1062	4	DODE A L	
MASP (Gas) (psi)	Max	x BHP-(0.12*	·C	otting Donth	<b>-</b>		=		quate For Drilling And Setting Casing at Depth?
, , , ,			_		_	1770	4	YES	air drill - rotating head
MASP (Gas/Mud) (psi)	Max	x BHP-(0.22*	.8	etting Depth	)=	527	4	YES	OK SI D
Pressure At Previous Shoe	May RHP_ 22*(Satting D	enth - Proviou	ne.	Shoe Denth	/=		=		Expected Pressure Be Held At Previous Shoe?
		epiii - Fieviou	us	Silve Depui	<i>,</i> –	1000	╣	NO NO	Reasonable
Required Casing/BOPE Te			_		_	2373	╝	psi	1 1/0 0
*Max Pressure Allowed @	Previous Casing Shoe=		_			40	Ш	psi *Assı	ımes 1psi/ft frac gradient
Calculations	Proc	l String	_			4.50	00	"	
Max BHP (psi)		.052*Settii	ng	g Depth*MW	7=	5790	1		
								BOPE Ade	quate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max	x BHP-(0.12*	S	etting Depth	)=	4721	j	YES	
MASP (Gas/Mud) (psi)	Max	x BHP-(0.22*	S	etting Depth	)=	3830	j	YES	ОК
								*Can Full	Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting D	epth - Previou	us	Shoe Depth	)=	4366		NO	Reasonable
Required Casing/BOPE To	est Pressure=					5000	l	psi	
*Max Pressure Allowed @	Previous Casing Shoe=					2432		psi *Assı	ımes 1psi/ft frac gradient
Calculations	S	tring	_				_	**	
Max BHP (psi)			ng	g Depth*MW	7=		╗		
			_			1	7	BOPE Ade	quate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max	x BHP-(0.12*	S	etting Depth	)=		7	NO	
MASP (Gas/Mud) (psi)	Max	x BHP-(0.22*	S	etting Depth	)=		7	NO	
							Ĩ	*Can Full	Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting D	epth - Previou	us	Shoe Depth	)=			NO	
Required Casing/BOPE To	est Pressure=		Ī				]	psi	
*Max Pressure Allowed @	Previous Casing Shoe=						Ī	psi *Assı	ımes 1psi/ft frac gradient
Calculations		tring	_					"	
Max BHP (psi)		tring 052*Setti	n	g Depth*MW	7=		=		
(Pos)		.032 5000		5 2 4 Pui 141 W	-	<u> </u>	4	BOPE Ade	quate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max	x BHP-(0.12*	S	etting Depth	)=		7	NO I	, games and games are septim
MASP (Gas/Mud) (psi)		x BHP-(0.22*)	_		-		╣	NO	
,, (F)		(52		<i>5</i> -r		<u> </u>	4	<u> </u>	Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting D	epth - Previou	us	Shoe Depth	)=		7	NO I	ī
Required Casing/BOPE Te			_		-		╣	psi	
						[!	4	1	

\*Max Pressure Allowed @ Previous Casing Shoe= psi \*Assumes 1psi/ft frac gradient

# 43047516140000 NBU 922-36C4BS



43047516140000 NBU 922-36C4BS Well name:

KERR-MCGEE OIL & GAS ONSHORE, L.P. Operator:

Surface Project ID: String type: 43-047-51614

**UINTAH** COUNTY Location:

Minimum design factors: **Environment:** Design parameters: H2S considered?

Collapse Collapse:

Surface temperature: Mud weight: 8.400 ppg Design factor 1.125

Design is based on evacuated pipe. Bottom hole temperature: 108 °F 1.40 °F/100ft Temperature gradient:

Minimum section length: 100 ft **Burst:** 

Cement top:

Non-directional string.

Design factor

**Burst** 

Max anticipated surface

pressure: 2,165 psi

0.120 psi/ft Internal gradient:

Calculated BHP 2,460 psi

No backup mud specified.

Tension:

8 Round STC:

1.80 (J) 8 Round LTC: 1.70 (J) 1.60 (J) Buttress:

Premium: 1.50 (J) Body yield: 1.50 (B)

Tension is based on air weight. Neutral point: 2,155 ft

Re subsequent strings: Next setting depth:

1.00

8,940 ft Next mud weight: 12.500 ppg Next setting BHP: 5,805 psi Fracture mud wt: 19.250 ppg Fracture depth: 2,460 ft

Injection pressure: 2,460 psi

No

1,352 ft

74 °F

Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length	Size	Weight	Grade	Finish	Depth	Depth	Diameter	Cost
	(ft)	(in)	(lbs/ft)			(ft)	(ft)	(in)	(\$)
1	2460	8.625	28.00	I-55	LT&C	2460	2460	7.892	97416
Run	Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension
Seq	Load	Strength	Design	Load	Strength	Design	Load	Strength	Design
•	(psi)	(psi)	Factor	(psi)	(psi)	Factor	(kips)	(kips)	Factor
1	1073	1880	1.751	2460	 3390	1.38	`68.9	`348	5.05 J

Helen Sadik-Macdonald Prepared

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: July 14,2011 Salt Lake City, Utah

Collapse is based on a vertical depth of 2460 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:

43047516140000 NBU 922-36C4BS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type:

Production

Project ID:

Location:

43-047-51614

UINTAH COUNTY

Minimum design factors:

**Environment:** 

Collapse

Mud weight:

Design parameters:

Internal fluid density:

Collapse: Design factor H2S considered?

Surface temperature:

Νo 74 °F 199 °F

1.000 ppg

12.500 ppg

Bottom hole temperature: Temperature gradient: Minimum section length:

1.40 °F/100ft

100 ft

**Burst:** 

Design factor

1.00 Cement top: 784 ft

**Burst** 

Max anticipated surface

Calculated BHP

pressure: Internal gradient:

No backup mud specified.

3,824 psi

0.220 psi/ft 5,784 psi

**Tension:** 

8 Round STC: 1.80 (J) 1.80 (J) 8 Round LTC: Buttress:

Premium: Body yield:

1.60 (J) 1.50 (J) 1.60 (B)

1.125

Directional Info - Build & Drop

Kick-off point 300 ft Departure at shoe: 406 ft Maximum dogleg: 2 °/100ft Inclination at shoe: 0 °

Tension is based on air weight.

Neutral point:

7,276 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	8940	4.5	11.60	I-80	LT&C	8907	8940	3.875	118008
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5321	6360	1.195	5784	7780	1.35	103.3	212	2.05 J

Prepared

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: July 14,2011 Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 8907 ft, a mud weight of 12.5 ppg. An internal gradient of .052 psi/ft was used for collapse from TD Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

# **ON-SITE PREDRILL EVALUATION**

# Utah Division of Oil, Gas and Mining

**Operator** KERR-MCGEE OIL & GAS ONSHORE, L.P.

Well Name NBU 922-36C4BS

API Number 43047516140000 APD No 3788 Field/Unit NATURAL BUTTES

**Location: 1/4,1/4** NENW **Sec** 36 **Tw** 9.0S **Rng** 22.0E 706 FNL 1749 FWL

GPS Coord (UTM) 637374 4428556 Surface Owner

# **Participants**

Floyd Bartlett (DOGM), Sheila Wopsock, Lovell Young, Gina Becker, Mark Koehn, Griz Oleen (Kerr McGee), Ben Williams (UDWR) and Mitch Batty, John Slaugh (Timberline Engineering and Land Surveying).

# Regional/Local Setting & Topography

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¾ mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 45.6 road miles following Utah State, Uintah County and oilfield development roads to the location.

Four additional gas wells will be added to and directionally drilled from the NBU 922-36C pad. They are the NBU 922-36C1CS, NBU 922-36C4BS, NBU 922-36F1BS and NBU 922-36F1CS. The pad contains the existing NBU 922-36C producing gas well. The existing pad will be significantly enlarged in all directions except to the southeast where a significant draw exists. The surface of the existing pad will be lowered about 6 inches to obtain the needed fill which extends from Location Corner 10 on the southeast to Corner 3 on the west. The reserve pit will be cut into slope on the north. Maximum cut is 11.2 feet at Corner 5 behind the reserve pit and maximum fill is 7.4 feet at Corner 2. No drainages will be intersected requiring diversions. The White River is approximately 1 1/4 miles to the west. The existing pad shows no stability problems and the site has no apparent concerns for constructing an enlarged pad and drilling and operating the planned wells. It is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA.

# Surface Use Plan

**Current Surface Use** 

Recreational Existing Well Pad

New Road Miles Well Pad Src Const Material Surface Formation

0 Width 352 Length 45 Onsite UNTA

**Ancillary Facilities** N

# **Waste Management Plan Adequate?**

#### **Environmental Parameters**

Affected Floodplains and/or Wetlands N

Flora / Fauna

7/26/2011 Page 1

Area beyond the existing pad is poorly vegetated with greasewood, cheatgrass, black sagebrush, broom snakeweed, globemallow, Sitanion hystrix, shadscale, rabbitbrush, pepper weed, halogeton and annuals.

Sheep, deer, antelope, coyote, and other small mammals and birds.

# **Soil Type and Characteristics**

Shallow rocky sandy loam.

**Erosion Issues** N

**Sedimentation Issues** N

Site Stability Issues N

**Drainage Diverson Required?** N

Berm Required? N

**Erosion Sedimentation Control Required?** N

Paleo Survey Run? Paleo Potental Observed? Cultural Survey Run? Y Cultural Resources? N

# **Reserve Pit**

Site-Specific Factors	Site R	anking	
Distance to Groundwater (feet)	100 to 200	5	
Distance to Surface Water (feet)	>1000	0	
Dist. Nearest Municipal Well (ft)	>5280	0	
Distance to Other Wells (feet)		20	
Native Soil Type	Mod permeability	10	
Fluid Type	Fresh Water	5	
Drill Cuttings	Normal Rock	0	
<b>Annual Precipitation (inches)</b>		0	
Affected Populations			
<b>Presence Nearby Utility Conduits</b>	Not Present	0	
	<b>Final Score</b>	40	1 Sensitivity Level

# **Characteristics / Requirements**

The reserve pit is planned in an area of cut in the northeast side of the location. Dimensions are 120' x 260' x 12' deep with 2' of freeboard. Because the length of time the reserve pit will be used and the roughness of the terrain, Kerr McGee committed to line it with a 30-mil.liner and an appropriate thickness of felt sub-liner to cushion the rock.

Closed Loop Mud Required? N Liner Required? Liner Thickness 30 Pit Underlayment Required? Y

# **Other Observations / Comments**

Floyd Bartlett 5/24/2011 **Evaluator Date / Time** 

7/26/2011 Page 2

# Application for Permit to Drill Statement of Basis

7/26/2011 Utah Division of Oil, Gas and Mining

Page 1

APD No	API WellNo	Status	Well Type	<b>Surf Owner</b>	<b>CBM</b>
3788	43047516140000	SITLA	GW	S	No
Operator	KERR-MCGEE OIL & GAS O	NSHORE, L.P.	<b>Surface Owner-APD</b>		
Well Name	NBU 922-36C4BS		Unit	NATURAL I	BUTTES
Field	NATURAL BUTTES		Type of Work	DRILL	
Location	NENW 36 9S 22E S 7	06 FNL 1749 F	WL GPS Coord (UTM)	637370E 4	428552N

# **Geologic Statement of Basis**

Kerr McGee proposes to set 2,640' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 2,500'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the proposed location. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement should adequately protect any usable ground water.

Brad Hill 6/20/2011 **APD Evaluator Date / Time** 

# **Surface Statement of Basis**

The general area is in the southeast portion of the Natural Buttes Unit, which contains the White River and rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¾ mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 42 air miles to the northwest. Access from Vernal is approximately 45.6 road miles following Utah State, Uintah County and oilfield development roads to the location.

Four additional gas wells will be added to and directionally drilled from the NBU 922-36C pad. They are the NBU 922-36C1CS, NBU 922-36C4BS, NBU 922-36F1BS and NBU 922-36F1CS. The pad contains the existing NBU 922-36C producing gas well. The existing pad will be significantly enlarged in all directions except to the southeast where a significant draw exists. The surface of the existing pad will be lowered about 6 inches to obtain the needed fill which extends from Location Corner 10 on the southeast to Corner 3 on the west. The reserve pit will be cut into slope on the north. Maximum cut is 11.2 feet at Corner 5 behind the reserve pit and maximum fill is 7.4 feet at Corner 2. No drainages will be intersected requiring diversions. The White River is approximately 1 1/4 miles to the west. The existing pad shows no stability problems and the site has no apparent concerns for constructing an enlarged pad and drilling and operating the planned wells. It is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA. Ed Bonner and Jim Davis of SITLA were invited to attend the pre-site evaluation. Neither attended. SITLA is to be contacted for reclamation standards including a seed mix to be used.

Ben Williams of the Utah Division of Wildlife Resources attended the pre-site. Mr. Williams stated no wildlife values would be significantly affected by drilling and operating the additional wells at this location.

Floyd Bartlett 5/24/2011
Onsite Evaluator Date / Time

# **Application for Permit to Drill Statement of Basis**

**Utah Division of Oil, Gas and Mining** 

Page 2

# **Conditions of Approval / Application for Permit to Drill**

**Category** Condition

7/26/2011

Pits A synthetic liner with a minimum thickness of 30 mils with a felt subliner shall be properly installed and maintained in the

reserve pit.

Surface The reserve pit shall be fenced upon completion of drilling operations.

# WORKSHEET APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 5/13/2011 **API NO. ASSIGNED:** 43047516140000

WELL NAME: NBU 922-36C4BS

**OPERATOR:** KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) **PHONE NUMBER:** 720 929-6086

**CONTACT:** Gina Becker

PROPOSED LOCATION: NENW 36 090S 220E **Permit Tech Review:** 

> SURFACE: 0706 FNL 1749 FWL **Engineering Review:**

> **BOTTOM: 0746 FNL 2153 FWL** Geology Review:

**COUNTY: UINTAH** 

**LATITUDE: 39.99788 LONGITUDE:** -109.39083

UTM SURF EASTINGS: 637370.00 NORTHINGS: 4428552.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 3 - State

LEASE NUMBER: ML-22650 PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

**SURFACE OWNER: 3 - State COALBED METHANE: NO** 

**RECEIVED AND/OR REVIEWED: LOCATION AND SITING:** 

✓ PLAT R649-2-3.

Unit: NATURAL BUTTES **Bond:** STATE/FEE - 22013542

**Potash** R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

**Drilling Unit** Oil Shale 190-13

Board Cause No: Cause 173-14 Water Permit: Permit #43-8496

**Effective Date:** 12/2/1999 **RDCC Review:** 

Siting: Suspends General Siting **Fee Surface Agreement** 

✓ Intent to Commingle R649-3-11. Directional Drill


**Commingling Approved** 

**Comments:** Presite Completed

Stipulations:

3 - Commingling - ddoucet 5 - Statement of Basis - bhill 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason 25 - Surface Casing - hmacdonald

API Well No: 43047516140000



# State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

# **Permit To Drill**

\*\*\*\*\*

**Well Name:** NBU 922-36C4BS **API Well Number:** 43047516140000

**Lease Number:** ML-22650 **Surface Owner:** STATE **Approval Date:** 7/26/2011

#### **Issued to:**

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

# **Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

#### **Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

# **Commingle:**

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

#### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

# **Conditions of Approval:**

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

API Well No: 43047516140000

# **Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan contact Dustin Doucet
- Significant plug back of the well contact Dustin Doucet
- Plug and abandonment of the well contact Dustin Doucet

# **Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well contact Carol Daniels OR
- submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at http://oilgas.ogm.utah.gov
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to cementing or testing casing contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well contact Dan Jarvis

# **Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 office
- Dustin Doucet 801-538-5281 office

801-733-0983 - after office hours

• Dan Jarvis 801-538-5338 - office

801-231-8956 - after office hours

# **Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) due prior to implementation
- Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
- Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas

	STATE OF UTAH		FORM 9
ι	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MINI		5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650
SUNDR	RY NOTICES AND REPORTS O	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	posals to drill new wells, significantly d reenter plugged wells, or to drill horizon n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36C4BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047516140000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	n Street, Suite 600, Denver, CO, 80217	<b>PHONE NUMBER:</b> 3779 720 929-0	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0706 FNL 1749 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	tip, range, Meridian: 36 Township: 09.0S Range: 22.0E Merid	ian: S	STATE: UTAH
11. CHECI	K APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
✓ SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud: 1/24/2012	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
1/24/2012	U TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
	WILDOAT WELL DETERMINATION	OTHER	OTHER:
	WILDCAT WELL DETERMINATION	OTHER	<u> </u>
MIRU TRIPPLE A BU	COMPLETED OPERATIONS. Clearly show al JCKET RIG. DRILLED 20" CON EDULE PIPE. CMT W/28 SX RE ON 01/24/2012 AT 0800 HF	DUCTOR HOLE TO 40'. EADY MIX. SPUD WELL	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY January 27, 2012
NAME (PLEASE PRINT)	PHONE NUMBE	R TITLE	
Sheila Wopsock	435 781-7024	Regulatory Analyst	
SIGNATURE N/A		<b>DATE</b> 1/25/2012	

# BLM - Vernal Field Office - Notification Form

	rator <u>KERR-McGEE OIL &amp; GA</u>			
Subr	nitted By SHEILA WOPSOCŁ	Phone Nur	nber <u>435.</u>	781.7024
	Name/Number NBU 922-360			
Qtr/0	Qtr <u>NE/NW</u> Section 36	Township g	<u>s</u> R	ange <u>22E</u>
Leas	e Serial Number ML-22650			
API I	Number <u>4304751614</u>			
-	d Notice – Spud is the initial pelow a casing string.	spudding c	of the we	ll, not drilling
	Date/Time <u>01/23/2012</u>	1100 HRS	AM 🗸	PM 🗌
<u>Casi</u> time	ng – Please report time cas s.	ing run star	ts, not ce	ementing
$\checkmark$	Surface Casing		R	ECEIVED
	Intermediate Casing		J	AN 2 0 2012
	Production Casing			
	Liner		DIV. OF	OIL, GAS & MINING
	Other			
	Date/Time <u>02/17/2012</u>	0800 HRS	AM 🗸	РМ
BOP	E Initial BOPE test at surface BOPE test at intermediate 30 day BOPE test Other			
	Date/Time		AM 🗌	PM
Rem	arks ESTIMATED DATE AND LOVEL YOUNG AT 435.	TIME. PLEA <del>781.7051 F</del> O	SE CONT R MORE	TACT

#### STATE OF UTAH **DEPARTMENT OF NATURAL RESOURCES** DIVISION OF OIL, GAS AND MINING

# **ENTITY ACTION FORM**

Operator:

KERR McGEE OIL & GAS ONSHORE LP

Operator Account Number: N 2995

1368 SOUTH 1200 EAST

Address:

city\_VERNAL

state UT zip 84078 Phone Number: (435) 781-7024

Well 1

API Number	Well N	lame	QQ	QQ Sec Twp		Rng County		
4304751613	NBU 922-36C1CS	:	NENW	36	98	22E	UINTAH	
Action Code	Current Entity Number	New Entity Number	S	Spud Date		Entity Assignment Effective Date		
A	99999	2900	1	/24/201	2	11	31 112	

SPUD WELL ON 01/24/2012 AT 01/24/2012 AT 1530 HRS.

Well 2

API Number	Well	Name	QQ	Sec	Twp	Rng	County
4304751614	NBU 922-36C4BS	922-36C4BS		NENW 36 9S		22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
A	99999	2900	1	/24/201	2	11	31 /10

Wall 2

API Number	Well I	Vame	QQ	QQ Sec Twp		p Rng Coun	
4304751616	NBU 922-36F1CS		NENW	NENW 36 9S Spud Date		22E	UINTAH
Action Code	Current Entity Number	New Entity Number	S			Entity Assignment Effective Date	
A	99999	2900	1	/23/201	2	\ I	31/12
	J TRIPPLE A BUCKET F D WELL ON 01/23/2012		II SEI	. y N			

#### **ACTION CODES:**

- A Establish new entity for new well (single well only)
- B Add new well to existing entity (group or unit well)
- Re-assign well from one existing entity to another existing entity
- Re-assign well from one existing entity to a new entity
- E Other (Explain in 'comments' section)

SHEILA WOPSOCK

Name (Please Print)

Signature

**REGULATORY ANALYST** 

1/25/2012

Title

Date

(5/2000)

JAN 2 5 2012

RECEIVED

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCE		FORM 9
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650		
SUNDR	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:		
Do not use this form for procurrent bottom-hole depth, FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES		
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36C4BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	NSHORE, L.P.		<b>9. API NUMBER:</b> 43047516140000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	h Street, Suite 600, Denver, CO, 8021	<b>PHONE NUMBER:</b> 7 3779 720 929-0	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0706 FNL 1749 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 36 Township: 09.0S Range: 22.0E Meri	idian: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT     Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
2/5/2012			
	WILDCAT WELL DETERMINATION	OTHER	OTHER:
MIRU AIR RIG ON FE RAN SURFACE CAS	COMPLETED OPERATIONS. Clearly show EBRUARY 4, 2012. DRILLED SING AND CEMENTED. WELL IDENTED. WELL IDENTED. COMPLETION REPORT.	SURFACE HOLE TO 2595'. IS WAITING ON ROTARY LUDED WITH WELL	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY February 07, 2012
NAME (PLEASE PRINT) Jaime Scharnowske	<b>PHONE NUME</b> 720 929-6304	BER TITLE Regulartory Analyst	
SIGNATURE N/A		<b>DATE</b> 2/6/2012	
		, _,	

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES		FORM 9					
ı	5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650							
SUNDR	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:							
	posals to drill new wells, significantly deep reenter plugged wells, or to drill horizontal n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES					
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36C4BS					
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047516140000					
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	PHO n Street, Suite 600, Denver, CO, 80217 377	ONE NUMBER: 79 720 929-6	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES					
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0706 FNL 1749 FWL			COUNTY: UINTAH					
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 36 Township: 09.0S Range: 22.0E Meridian:	: S	STATE: UTAH					
11. CHECI	K APPROPRIATE BOXES TO INDICATE N	IATURE OF NOTICE, REPOR	T, OR OTHER DATA					
TYPE OF SUBMISSION		TYPE OF ACTION						
✓ NOTICE OF INTENT	ACIDIZE	ALTER CASING	CASING REPAIR					
Approximate date work will start:	✓ CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME					
2/23/2012	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE					
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION					
Bate of Work Completion.	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK					
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION					
SPUD REPORT Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON					
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL					
DRILLING REPORT	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION					
Report Date:	WILDCAT WELL DETERMINATION	OTHER	OTHER:					
12 DESCRIBE PROPOSED OR		ertinent details including dates, d	enths volumes etc					
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  The operator requests approval for changes in the drilling plan.  Specifically, the Operator requests approval for a FIT waiver, closed loop drilling option, and a production casing change. All other aspects of the previously approved drilling plan will not change. These proposals do not deviate from previously submitted and approved plans. Please see attachments. Thank you.  Approved by the Utah Division of Oil, Gas and Mining  Date: February 29, 2012								
,		,	<b>-</b> ,					
NAME (PLEASE PRINT) Jaime Scharnowske	<b>PHONE NUMBER</b> 720 929-6304	TITLE Regulartory Analyst						
SIGNATURE	,	DATE						
N/A		2/23/2012						

NBU 922-36C4BS Drilling Program
1 of 7

# Kerr-McGee Oil & Gas Onshore. L.P.

# NBU 922-36C4BS

Surface: 706 FNL / 1749 FWL NENW BHL: 746 FNL / 2153 FWL NENW

Section 36 T9S R22E

Uintah County, Utah Mineral Lease: ML-22650

#### ONSHORE ORDER NO. 1

#### **DRILLING PROGRAM**

# 1. & 2. <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1350'	
Birds Nest	1,652'	Water
Mahogany	2,008'	Water
Wasatch	4,466'	Gas
Mesaverde	6,680'	Gas
MVU2	7,651'	Gas
MVL1	8,256'	Gas
TVD	8,907'	
TD	8.940'	

# 3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Drilling Program

# 4. <u>Proposed Casing & Cementing Program:</u>

Please refer to the attached Drilling Program

# 5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

# 6. <u>Evaluation Program</u>:

Please refer to the attached Drilling Program

NBU 922-36C4BS Drilling Program
2 of 7

#### 7. **Abnormal Conditions:**

Maximum anticipated bottom hole pressure calculated at 8907' TVD, approximately equals 5,700 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,728 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

#### 8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

#### 9. <u>Variances:</u>

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- · Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

# **Background**

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

RECEIVED: Feb. 23, 2012

NBU 922-36C4BS Drilling Program
3 of 7

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

# Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

#### **Variance for Mud Material Requirements**

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

#### Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 922-36C4BS Drilling Program
4 of 7

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

# Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

#### Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

#### 10. Other Information:


Please refer to the attached Drilling Program.

NBU 922-36C4BS Drilling Program
5 of 7



# KERR-McGEE OIL & GAS ONSHORE LP <u>DRILLING PROGRAM</u>

COMPANY NAME KER	R-McGEE O	IL & GAS ONSI	HORE LP		DATE	February 23, 2012			
WELL NAME NBU 922-36C4BS					TD	8,907'	TVD	8,940' MD	
FIELD Natural Butte	S	COUNTY Uintah STATE Utal			1	FINISH	5,096'		
SURFACE LOCATION	NENW	706 FNL	1749 FWL	Sec 36	T 9S	R 22E			
	Latitude:	39.997876	Longitude:	-109.390	809		NAD 27		
BTM HOLE LOCATION	NENW	746 FNL	2153 FWL	Sec 36	T 9S	R 22E			
	Latitude:	39.997763	Longitude:	-109.389	367		NAD 27		
OBJECTIVE ZONE(S)	Wasatch/M	lesaverde	•	•	•				
ADDITIONAL INFO	Pagulaton, Agancias IIDOCM (Minarala), IIDOCM (Surface), IIDOCM Tri County Hoolth Dont								



**Drilling Program** NBU 922-36C4BS



# KERR-McGEE OIL & GAS ONSHORE LP

6 of 7

**DESIGN FACTORS** 



**CASING PROGRAM** 

**DRILLING PROGRAM** 

CONDUCTOR
SURFACE

**PRODUCTION** 

									LIC	DQX
SIZE	INTERVAL			WT.	GR.	CPLG.	BURST	COLLAPSE		TENSION
14"	0-40'									
							3,390	1,880	348,000	N/A
8-5/8"	0	to	2,460	28.00	IJ-55	LTC	2.20	1.63	5.77	N/A
							7,780	6,350	223,000	267,035
4-1/2"	0	to	5,000	11.60	I-80	DQX	1.11	1.10		3.18
4-1/2"	5,000	to	8,940'	11.60	I-80	LTC	1.11	1.10	6.03	

**Surface Casing:** 

(Burst Assumptions: TD = 12.5 0.73 psi/ft = frac gradient @ surface shoe ppg)

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

Production casing:

7000 psi) 0.64 psi/ft = bottomhole gradient (Burst Assumptions: Pressure test with 8.4ppg @

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

#### CEMENT PROGRAM

	FT. OF FILL	LL DESCRIPTION		EXCESS	WEIGHT		YIELD	
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80		1.15	
Option 1		+ 0.25 pps flocele						
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80		1.15	
		+ 2% CaCl + 0.25 pps flocele						
SURFACE		NOTE: If well will circulate water	to surface,	option 2 wi	II be utilized			
Option 2 LEAD	1,960'	65/35 Poz + 6% Gel + 10 pps gilsonite	180	35%	11.00		3.82	
		+ 0.25 pps Flocele + 3% salt BWOW						
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80		1.15	
		+ 0.25 pps flocele						
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80		1.15	
PRODUCTION LEAD	3,960'	Premium Lite II +0.25 pps	310	35%	12.00		3.38	
		celloflake + 5 pps gilsonite + 10% gel						
		+ 0.5% extender						
TAIL	4,980'	50/50 Poz/G + 10% salt + 2% gel	1,180	35%	14.30		1.31	
		+ 0.1% R-3						

<sup>\*</sup>Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

#### **FLOAT EQUIPMENT & CENTRALIZERS**

**SURFACE** 

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

**PRODUCTION** 

Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well.

1 centralizer on the first 3 joints and one every third joint thereafter.

#### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.


DRILLING ENGINEER: DATE: Nick Spence / Danny Showers / Chad Loesel DRILLING SUPERINTENDENT: DATE:

Kenny Gathings / Lovel Young

<sup>\*</sup>Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

Sundry Number: 23272 API Well Number: 43047516140000

EXHIBIT A NBU 922-36C4BS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK

Sundry Number: 23272 API Well Number: 43047516140000

#### Requested Drilling Options:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

RECEIVED: Feb. 23, 2012

Sundry Number: 23966 API Well Number: 43047516140000

	STATE OF UTAH		FORM 9
ı	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MIN		5.LEASE DESIGNATION AND SERIAL NUMBER: ML-22650
SUNDR	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	oposals to drill new wells, significantly reenter plugged wells, or to drill horizo n for such proposals.		7.UNIT OF CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-36C4BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047516140000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	h Street, Suite 600, Denver, CO, 8021	<b>PHONE NUMBER:</b> 7 3779 720 929-	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0706 FNL 1749 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 36 Township: 09.0S Range: 22.0E Meri	dian: S	STATE: UTAH
11. CHECK	K APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT     Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
3/16/2012	_		OTHER:
	WILDCAT WELL DETERMINATION	UTHER	
MIRU ROTARY RI MARCH 14, 201 CEMENTED PROI MARCH 16, 2012 INCLUDED WITH THI	COMPLETED OPERATIONS. Clearly show IG. FINISHED DRILLING FRO 2. RAN 4-1/2" 11.6# I-80 PR DUCTION CASING. RELEASEI @ 06:00 HRS. DETAILS OF CE WELL COMPLETION REPORTINAL COMPLETION ACTIVIT	M 2,595' TO 8,955' ON ODUCING CASING. D ENSIGN 138 RIG ON EMENT JOB WILL BE RT. WELL IS WAITING ON	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 20, 2012
NAME (5)		SED TITLE	
NAME (PLEASE PRINT) Jaime Scharnowske	<b>PHONE NUME</b> 720 929-6304	BER TITLE Regulartory Analyst	
SIGNATURE N/A		<b>DATE</b> 3/17/2012	

# State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# Ensign 138 Submitted By BRAD PEDERSEN Phone Number 435- 828- 0982 Well Name/Number NBU 922-36C4BS Qtr/Qtr NE/SW Section 36 Township 9S Range 22E Lease Serial Number ML-22650 API Number43-047-51614	
<u>Casing</u> – Time casing run starts, not cementing times.	
Production Casing Other	
Date/Time AM PM RECEIVE	ED
BOPE Initial BOPE test at surface casing point Other  MAR 1 3 201	-
Date/Time 07:00 AM $igtriangleq$ PM $igcap$	
Rig Move Location To: BONANZA 922-36C4BS	
Date/Time <u>3/11/2012</u> <u>06:00</u> AM ⊠ PM □	
Remarks TIME IS ESTIMATED	

# State of Utah - Notification Form

Operator <u>Anadarko Petroleum</u> Rig Name/# <u>Ensign 13</u> Submitted By <u>BRAD PEDERSEN</u> Phone Number <u>43</u> 0982 Well Name/Number <u>NBU 922-36C4BS</u> Qtr/Qtr <u>NW/NE</u> Section <u>36</u> Township <u>9S</u> Range 22E	<u>8</u> 35- 828-
Lease Serial Number ML-22650  API Number43-047-51614	
<u>Casing</u> – Time casing run starts, not cementing times.	
<ul><li>Production Casing</li><li>Other</li></ul>	
Date/Time <u>3/15/2012</u> <u>09:00</u> AM ⊠ PM □	
BOPE	RECEIVED
<ul><li>Initial BOPE test at surface casing point</li><li>Other</li></ul>	MAR 1 4 2012 V. OF OIL, GAS & MINING
Date/Time AM PM D	
Rig Move Location To: NBU 922-36FICS	
Date/Time <u>3/8/2012</u> <u>14:00</u> AM ☐ PM ⊠	
Remarks <u>TIME IS ESTIMATED</u>	

#### STATE OF UTAH AMENDED REPORT FORM 8 DEPARTMENT OF NATURAL RESOURCES (highlight changes) DIVISION OF OIL, GAS AND MINING 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-22650 6. IF INDIAN, ALLOTTEE OR TRIBE NAME WELL COMPLETION OR RECOMPLETION REPORT AND LOG 1a. TYPE OF WELL: 7. UNIT or CA AGREEMENT NAME OTHER UTU63047A 8. WELL NAME and NUMBER: b. TYPE OF WORK: HORIZ. DIFF. RESVR RE-ENTRY NBU 922-36C4BS OTHER 2. NAME OF OPERATOR 9. API NUMBER: KERR MCGEE OIL & GAS ONSHORE, L.P. 4304751614 3. ADDRESS OF OPERATOR: 10 FIELD AND POOL, OR WILDCAT PHONE NI IMBER: P.O.BOX 173779 STATE CO ZIP 80217 (720) 929-6000 NATURAL BUTTES CITY **DENVER** 11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: 4. LOCATION OF WELL (FOOTAGES) AT SURFACE: NENW 706 FNL 1749 FWL S36, T9S, R22E NENW 36 9S 22E S AT TOP PRODUCING INTERVAL REPORTED BELOW: NENW 734 FNL 2137 FWL S36, T9S, R22E 12. COUNTY 13. STATE AT TOTAL DEPTH: NENW 761 FNL 2163 FWL S36, T9S, R22E BHI WY HSW **UTAH** UINTAH 15. DATE T.D. REACHED: 16. DATE COMPLETED: 14. DATE SPUDDED: 17. ELEVATIONS (DF, RKB, RT, GL): ABANDONED T READY TO PRODUCE [7] 1/24/2012 3/14/2012 5/9/2012 5096 GL 19. PLUG BACK T.D.: MD 8.894 18. TOTAL DEPTH: MD 21. DEPTH BRIDGE MD 8.955 20. IF MULTIPLE COMPLETIONS, HOW MANY? PLUG SET: TVD 8.925 TVD 8.864 TVD 22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) WAS WELL CORED? NO 🔽 YES (Submit analysis) BHP-HDIL/ZDL/CNGR-CBL/GR/COLLARS WAS DST RUN? NO 🗸 YES (Submit report) DIRECTIONAL SURVEY? NO YES 🗸 (Submit copy) 24. CASING AND LINER RECORD (Report all strings set in well) STAGE CEMENTER **CEMENT TYPE &** SLURRY TOP (MD) BOTTOM (MD) CEMENT TOP \*\* AMOUNT PULLED HOLE SIZE SIZE/GRADE WEIGHT (#/ft ) NO. OF SACKS DEPTH VOLUME (BBL) 20" STL 36.7# O 40 28 11" 8 5/81 **IJ-55** 28# 0 2,587 600 0 7 7/8" 4 1/2" 1-80 11.6# 0 8,938 1,427 536 25. TURING RECORD DEPTH SET (MD) PACKER SET (MD) SIZE DEPTH SET (MD) PACKER SET (MD) SIZE DEPTH SET (MD) PACKER SET (MD) SIZE 2 3/8" 8.250 26. PRODUCING INTERVALS 27. PERFORATION RECORD FORMATION NAME TOP (MD) BOTTOM (MD) TOP (TVD) BOTTOM (TVD) INTERVAL (Top/Bot - MD) SIZE NO. HOLES PERFORATION STATUS 7,076 8,750 (A) MESAVERDE 7.076 8.750 0.36 168 Open Squeezed (B) Open Squeezed (C) Open Squeezed (D) 28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC. DEPTH INTERVAL AMOUNT AND TYPE OF MATERIAL 7076-8750 PUMP 7934 BBLS SLICK H2O & 187,309 LBS 30/50 OTTAWA SAND DIV. OF OIL, GAS & MIN 7 STAGES 29. ENCLOSED ATTACHMENTS: 30. WELL STATUS: ✓ DIRECTIONAL SURVEY ELECTRICAL/MECHANICAL LOGS GEOLOGIC REPORT DST REPORT PROD SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION CORE ANALYSIS OTHER:

31.	IN	ITIAL	PRODUCTI	ON
DAT	ΓE	FIRST	PRODUCE	D:

TEST DATE:

#### INTERVAL A (As shown in item #26)

RATES:

TEST PRODUCTION | OIL - BBL:

GAS - MCF:

WATER - BBL:

PROD. METHOD:

HOURS TESTED:

5/9/2012		5/10/	2012		2	<u>2</u> 4	RATES: →	0	1,217	99	0	
CHOKE SIZE: 20/64	TBG. PRESS 850	. CSG. PR 1,40		API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF: 1,217	WATER - 99		INTERVAL STATUS: PROD
				•	INT	ERVAL B (As show	wn in item #26)					
DATE FIRST PRO	ODUCED:	TEST DA	TE:		HOURS TESTED	:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER -	BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS	. CSG. PR	ESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	N OIL BBL:	GAS - MCF:	WATER	BBL:	INTERVAL STATUS:
					INTI	ERVAL C (As show	wn in item #26)					
DATE FIRST PRO	ODUCED:	TEST DA	TE:		HOURS TESTED	:	TEST PRODUCTION RATES: →	OIL - BBL:	GAS MCF:	WATER -	BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS	. CSG. PR	ESS.	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	N OIL - BBL:	GAS - MCF:	WATER -	BBL:	INTERVAL STATUS:
					INT	RVAL D (As show	wn in Item #26)					
DATE FIRST PRO	ATE FIRST PRODUCED: TEST DATE:				HOURS TESTED: TEST PRODU RATES: →			I OIL - BBL:	GAS MCF:	WATER	BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS	. CSG. PR	ESS.	API GRAVITY	BTU GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	N OIL - BBL:	GAS - MCF:	WATER -	BBL:	INTERVAL STATUS:
32. DISPOSITIO	N OF GAS (So	old, Used for F	uel, Ven	ited, Etc.)			•					
33. SUMMARY	OF POROUS Z	ONES (Includ	e Aquife	ers):	**		3	34. FORMATION	(Log) MARKERS:		<del></del>	
Show all importar tested, cushion u					als and all drill-stem recoveries.	tests, including de	pth interval					
Formatio	on .	Top (MD)	Bott (M	tom D)	Descript	ions, Contents, etc			Name		(1	Top Measured Depth)
								GREEN RI BIRD'S NE MAHOGAN WASATCH MESAVER	ST IY I			1,369 1,669 2,138 4,492 6,657

35. ADDITIONAL REMARKS (Include plugging procedure)

The first 210' of the surface hole was drilled with a 12 1/4" bit. The remainder of surface hole was drilled with an 11" bit. DQX csg was run from surface to 4991'; LTC csg was run from 4991' to 8938'. Attached is the chronological well history, perforation report & final survey.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) CARA MAHLER SIGNATURE

REGULATORY ANALYST

DATE

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- · significantly deepening an existing well bore below the previous bottom-hole depth
- · drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\*\* ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining

1594 West North Temple, Suite 1210

Box 145801

Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

<sup>\*</sup> ITEM 20: Show the number of completions if production is measured separately from two or more formations.

# **Operation Summary Report**

 Well: NBU 922-36C4BS BLUE
 Spud Date: 2/4/2012

 Project: UTAH-UINTAH
 Site: NBU 922-36C PAD
 Rig Name No: PROPETRO 12/12, ENSIGN 138/138

 Event: DRILLING
 Start Date: 11/22/2011
 End Date: 3/16/2012

Active Datum: RKB @5,110.01ft (above Mean Sea

UWI: NE/NW/0/9/S/22/E/36/0/0/26/PM/N/706/W/0/1749/0/0

Level)	4. 0. 0							
Date	1. S. Grenning 1990 a	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (ft)
2/4/2012	4:00	- 8:45	4.75	MIRU	01	С	Р	INSTALL DIVERTER HEAD AND BLOOIE LINE, BUILD DITCH, SPOT IN RIG, CATWALK AND PIPE RACKS RIG UP HOLE PUMP. INSPECT RIG. SUFFICIENT WATER VOLUME IS PRESENT IN RESERVE.
	8:45	- 9:15	0.50	PRPSPD	01	В	<b>P</b>	HELD PJSM. P/U 8" 1.83 BEND .17 RPG MUD MOTOR ( 3rd RUN) (SN 800-3017). M/U QD507 12.25" BIT ( 4th RUN) (SN 711370662). P/U USED SHOCK SUB SN (160-80488). TRIP IN CONDUCTOR TO SPUD.
	9:15	- 10:15	1.00	DRLSUR	02	D	P	SPUD 02/04/2012 09:15. DRILL 12.25" HOLE 44'- 210' (166', 140'/HR). GPM 400. DH RPM 68 RPM=45, WOB 5-15 Kips. PSI ON/OFF 600/400. UP/DOWN/ ROT 20/20/20 K. DRAG 0 Kips. CIRC RESERVE W. 8.4 ppg WATER. DRILL DOWN TO 210' W/ 6" COLLARS.
	10:15	- 10:45	0.50	DRLSUR	05	Α	Þ	C&C HOLE COMBINED WITH RIG SERVICE TIME
	10:45	- 12:30	1.75	DRLSUR	06	Α	Р	TRIP OUT. LAY DOWN 6" DRILL COLLARS, 12 1/4 BIT. CHECK BIT AND MOTOR. PICK UP Q506 11" BIT ( 2nd RUN) (SN 7029500) P/U 8" DIRECTIONAL ASSEMBLY. INSTALL EM TOOL. TRIP IN TO 210' TO DRILL AHEAD.
		- 0:00	11.50	DRLSUR	02	D	P	DRILL 11" HOLE 210'-1570', CIRC RESERVE W. 8.3 ppg WATER. ROTATING HOURS 12.5 / 1575 ft. = 125fph. NO HOLE ISSUES.
2/5/2012	0:00	- 12:00	12.00	DRLSUR	02	D	Р	DRILL FROM 1360 ft. TO TD AT 2595 ft.
		- 14:00	2.00	DRLSUR	05	A	P	CIRCULATE AND CLEAN HOLE, PREPARE FOR TOOH.
1		- 16:15	2.25	DRLSUR	06	D	Р	LDDS FOR CASING RUN
		- 18:30	2.25	DRLSUR	06	D	Р	LAY DOWN DIRECTIONAL TOOLS. PULL MOTOR AND BREAK BIT. LAY DOWN MOTOR.
	18:30	- 20:30	2.00	DRLSUR	12	Α	P	MOVE PIPE RACKS AND CATWALK. PULL DIVERTER HEAD. RIG UP TO RUN CASING. RUN 200 ft. 1 INCH.
	20:30	- 22:00	1.50	DRLSUR	12	<b>C</b>	P	HOLD PJSM, RUN 59 JNT'S OF 8-5/8" 28# J-55 LTC CSG. LAND FLOAT SHOE @ 2572' KB. LAND BAFFLE PLATE @ 2525' KB. RAN 5 TOTAL CENTRALIZERS.
	22:00	- 22:30	0.50	DRLSUR	12	E	P	PRESSURE TEST LINES TO 2500 PSI. PUMP 50 BBLS OF WATER AHEAD. MIX AND PUMP 20 BBLS OF 8.3# GEL WATER AHEAD. MIX AND PUMP (300 SX) 157 BBLS OF 15.8# 1.15 YD 5 GAL/SK PREMIUM CEMENT W/ 2% CALC. DROP PLUG ON FLY. DISPLACE W/ 157 BBLS OF H20. NO RETURNS THROUGH OUT JOB. FINAL LIFT OF 220 PSI AT 3 BBL/MIN. BUMP PLUG AT DISPLACEMENT VOLUME. LAND THE PLUG WITH 800 PSI. SHUT DOWN HELD 800 PSI FOR 5 MIN. TESTED FLOAT AND FLOAT HELD.

# **Operation Summary Report**

Well: NBU 922-36C4BS BLUE Spud Date: 2/4/2012

Project: UTAH-UINTAH Site: NBU 922-36C PAD Rig Name No: PROPETRO 12/12, ENSIGN 138/138

End Date: 3/16/2012

Event: DRILLING Start Date: 11/22/2011

Active Datum: R	KB @5,1	10.01ft (abo	ve Mean Sea		UWI: NE/NW/0/9/S/22/E/36/0/0/26/PM/N/706/W/0/1749/0/0							
Date	A	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation (ft)				
	22:30	- 23:00	0.50	DRLSUR	12	E	P	TOP OUT CEMENT DOWN BACKSIDE w/ 150 sx. (61.4 bbls.) SAME TAIL CEMENT WITHOUT RETURNS TO SURFACE, WOC 2 HOURS. TOP OUT CEMENT DOWN BACKSIDE w/ 150sx. (61.4 bbls.) SAME TAIL CEMENT WITHOUT RETURNS TO SURFACE. WILL TOP AGAIN ON NEXT WELL. RIG DOWN CEMENTERS. TOC ESTIMATED AT 450 ft.				
	23:00	- 0:00	1.00	RDMO	01	Α	P	RD/ RIG RELEASE AT 0000 hrs. 2-5-2012				
3/11/2012	6:00	- 7:00	1.00	MIRU	01	С	Р	SKID RIG, RIG UP ROTARY TOOLS				
	7:00	- 7:30	0.50	MIRU	14	Α	Р	NIPPLE UP BOP				
	7:30	- 13:00	5.50	DRLPRO	15	A	Р	SAFETY MEETING W/ A-1 TESTING, R/U & TEST BOP , FLOOR VALVES, INSIDE & OUT SIDE KILL LINE & CHOKE LINE VALVES, HCR VALVE, CHOKE MANIFOLD, PIPE RAMS & BLIND RAMS 250 PSI F/ 5 MIN ,5000 PSI F/ 10 MIN, ANNULAR 250 PSI F/ 5 MIN, 2500 PSI F/ 10 MIN & CASING TO 1500 PSI F/ 30 MIN , RIG DOWN TESTER				
	13:00	- 14:30	1.50	DRLPRO	09	Α	P	SLIP & CUT 105' DRILL LINE				
	14:30	- 15:00	0.50	DRLPRO	14	В	P	INSTALL WEAR BUSHING				
	15:00	- 15:30	0.50	DRLPRO	07	Á	P	RIG SERVICE, LUBE RIG ,CHANGE GRIPPER RAM ON IRON DERRICKMAN				
	15:30	- 19:00	3.50	DRLPRO	06	Α	Р	PICK UP SMITH MDI 616 BIT, SDI .28 RPG/ 1.5 BEND MOTOR, ORIENT MWD, TIH, TAG CEMENT @ 2490'				
	19:00	- 20:00	1.00	DRLPRO	02	F	Р	DRILL CEMENT & FLOAT EQUIP F/ 2490' TO 2605', SPUD @ 19:00 3/11/2012				
	20:00	- 20:30	0.50	DRLPRO	02	Ð	Р	DRILL ,SLIDE, SURVEY F/ 2605' TO 2736 131' @ 262' HR				
	20:30	- 21:00	0.50	DRLPRO	22	L	Z	TROUBLE SHOOT MWD TOOL				
		- 0:00	3.00	DRLPRO	02	D	P	DRILL, SLIDE ,SURVEY F/ 2736'; TO 3143' 407' @ 135.6' HR WOB 15/17 RPM 55/151, SPM 120 / GPM 540 TORQ 8/4 ON/OFF 1500/1000 UP/SO/ROT 105/95/100 WT 8.4 / VIS 28 SLIDE .25 HRS, 36' @ 144' HR NOV DEWATERING				
3/12/2012	0:00	- 1:00	1.00	DRLPRO	02	D	P	DRILL, SLIDE, SURVEY F/ 3143' TO 3249' 106' @ 106' HR WOB 15/17 RPM 55/151, SPM 120 / GPM 540 TORQ 8/4 ON/OFF 1500/1000 UP/SO/ROT 105/95/100 WT 8.4 / VIS 28				
								SLIDE .67 HRS, 48' @ 71.6' HR NOV DEWATERING				
	1:00	- 2:00	1.00	DRLPRO	22	L	<b>Z</b> .	TROUBLE SHOOT MWD, TOOL FAILURE				
	2:00	- 4:30	2.50	DRLPRO	06	Н	Z	TRIP OUT OF HOLE F) MWD FAILURE				
	4:30	- 6:00	1.50	DRLPRO	22	L	Z	CHANGE MWD TOOLS OUT & CHECK HIGH SIDE				
1	6:00	- 8:00	2.00	DRLPRO	06	Н	Z	TRIP IN HOLE				

6/20/2012

9:33:39AM

# **Operation Summary Report**

 Well: NBU 922-36C4BS BLUE
 Spud Date: 2/4/2012

 Project: UTAH-UINTAH
 Site: NBU 922-36C PAD
 Rig Name No: PROPETRO 12/12, ENSIGN 138/138

 Event: DRILLING
 Start Date: 11/22/2011
 End Date: 3/16/2012

Active Datum: RKB @5,110.01ft (above Mean Sea

UWI: NE/NW/0/9/S/22/E/36/0/0/26/PM/N/706/W/0/1749/0/0

ctive Datum: R evel)	(50,	, , , , , , , , , , , , , , , , , , , ,			UVVI: NE/NVVIOI9151227E/35/0/0/26/PWIN/106/VVIO/1149/0/0							
Date		Time	Duration	Phase	Code	Sub	P/U MD From	Operation				
		art-End	(hr)	***		Code	(ft)					
	8:00	- 8:30	0.50	DRLPRO	07	A	P	RIG SERVICE				
	8:30	- 18:00	9.50	DRLPRO	02	D	Р	DRILL, SLIDE, SURVEY F/ 3249' TO 4536'				
								1287' @ 135.4				
								WOB 18-20				
								RPM 55/151,				
								SPM 120 / GPM 540				
								TORQ 8/4				
								ON/OFF 1860/1150 UP/SO/ROT 130/126/129				
								WT 8.3 / VIS 27				
								SLIDE . 1.51 HRS, 165' @ 109.2' HR				
								NOV DEWATERING				
	18:00	- 0:00	6.00	DRLPRO	02	D		DRILL, SLIDE, SURVEY F/ 4536' TO 5444'				
								908' @ 151.3' HR				
								WOB 18-20				
								RPM 55/151,				
								SPM 120 / GPM 540				
								TORQ 11/6				
								ON/OFF2200/1650				
								UP/SO/ROT 165/145/150				
								WT 8.3 / VIS 27				
								SLIDE75 HRS, 70' @ 93.3' HR				
								NOV DEWATERING				
3/13/2012	0:00	- 5:30	5.50	DRLPRO	02	D	Р	DRILL, SLIDE, SURVEY F/ 5444' TO 6150'				
								706' @ 128.3' HR				
								WOB 18/20				
								RPM 55/151,				
								SPM 120 / GPM 540				
								TORQ 11/6 ON/OFF 2200/1650				
								UP/SO/ROT 165/145/150				
								WT 8.3 / VIS 27				
								BIT POSITION 8.36 N, 8.21 W				
								SLIDE 0				
								NOV DEWATERING				
	5:30	- 6:00	0.50	DRLPRO	08	Α	Z	RIG REPAIR, #1 GENERATOR DOWN DUE TO LOW				
								GAS PRESSURE, TROUBLE SHOOT PROBLEM				
	6:00	- 15:00	9.00	DRLPRO	02	D	Р	DRILL, SLIDE, SURVEY F/ 6150' TO 7273'				
								1123' @ 124.7' HR				
								WOB 18/20				
								RPM 55/138				
								SPM 110 / GPM 495				
								TORQ 11/6				
	,							ON/OFF 2269/1705				
								UP/SO/ROT 171/148/159				
								WT 9.5 / VIS 30				
								BIT POSITION 11.38 N, 15.18 W				
								SLIDE .99 HRS, 87' @ 87.8' HR NOV SHUT DOWN DEWATERING @ 7000				
								START MUD UP, RUN CENTRAFUGE 1.5 HRS EVERY				
								3 HOURS				
		- 15:30	0.50	DRLPRO	07	Α	P	RIG SERVICE				

6/20/2012

# **Operation Summary Report**

 Well: NBU 922-36C4BS BLUE
 Spud Date: 2/4/2012

 Project: UTAH-UINTAH
 Site: NBU 922-36C PAD
 Rig Name No: PROPETRO 12/12, ENSIGN 138/138

 Event: DRILLING
 Start Date: 11/22/2011
 End Date: 3/16/2012

Vent. DRILLING				Start Date				End Date: 3/10/2012
ctive Datum: RK evel)	B @5,1	10.01ft (abo\	/e Mean Sea		UWI: NE	E/NW/0/9/	/S/22/E/3	6/0/0/26/PM/N/706/W/0/1749/0/0
evel) Date		Time	Duration	Phase	Code	Sub	P/U	MD From Operation
	St	art-End	(hr)			Code		(m)
	15:30	- 0:00	8.50	DRLPRO	02	D	P	DRILL, SLIDE, SURVEY F/7273' TO 7844'
								571' @ 67.1' HR
								WOB 18/20
		*						RPM 55/126
								SPM 110 / GPM 450
								TORQ 15/9
								ON/OFF2929/ 2500
								UP/SO/ROT180/149/163
								WT 11 / VIS 38
								BIT POSITION @ 7844' 11.62' N, 9.5' W
								SLIDE 2.92 HRS , 110' @ 37.6' HR
								NOV RUNNING 1.5 HRS EVERY 3 HOURS
3/14/2012	0:00	- 9:30	9.50	DRLPRO	02	D	Р	DRILL F/ 7844' TO 8502', 658' @ 69.3'/HR
								WOB 18-20,
								SPM 110, GPM 496
								RPM 50/139,
								MUD 39 /VIS, 11.3/ WT.
								TRQ ON/OFF 15/12
								PSI ON/OFF , 3085/2535
								PU/SO/ROT 192/163/172
								SLIDE: 0'
								NOV RUNNING:CONVENTIONAL @ 30% 11/2
								HOUR ON 3 OFF
								BIT POSITION: 1.9'W 3.09'N OF CENTER
								RUNNING LCM TO CONTROL SEEPING LOST APP.
	9:30	40.00	0.50	MANINE	07	۸		80 BBL, OF FLUID
		- 10:00	0.50	MAINT	07	A	P	RIG SERVICE
	10.00	- 15:00	5.00	DRLPRO	02	D	P	DRILL F/ 8502'-8955', 453' @ 90.6'/HR
								WOB 18-20,
								SPM 110, GPM 496
								RPM 50/139,
								MUD 39 /VIS, 11.3/ WT.
								TRQ ON/OFF 15/12 PSI ON/OFF , 3085/2535
								PU/SO/ROT 194/163/175
								SLIDE: 0'
								NOV RUNNING:CONVENTIONAL @ 30% 11/2
								HOUR ON 3 OFF
								BIT POSITION: 9.74'E 14.16'S OF CENTER
								RUNNING LCM TO CONTROL SEEPING LOST APP.
								40 BBL. OF FLUID
	15:00	- 16:30	1.50	DRLPRO	05	Ċ	Þ	CIRCULATED PRIOR TO THE WIPER TRIP
	16:30	- 0:00	7.50	DRLPRO	06	E	Р	PUMPED 1 STAND OFF BOTTOM AND MADE A
					-	•		WIPER TRIP TO THE CASING SHOE PRIOR TO
								ATTEMPTING TO RUN LOGS,WE HAD ONE TIGHT
								SPOT AT 4420'. FILL THE PIPE AT THE CASING
								SHOE AND 5100'
3/15/2012	0:00	- 1:30	1.50	DRLPRC	06	E	P	FINISH TRIPPING IN THE HOLE ON THE WIPER TRIP.
						_	-	69 STANDS TOTAL
	1:30	- 3:30	2.00	DRLPRC	05	С	P	CIRCULATE AND CONDITION FOR LOGS, 2/10 GAS
						~	-	CUT ON BOTTOMS UP NO FLARE
	3:30	- 10:00	6.50	DRLPRC	06	В	P	TRIP OUT OF THE HOLE TO RUN LOGS, LAY DOWN

# **Operation Summary Report**

Spud Date: 2/4/2012 Well: NBU 922-36C4BS BLUE

Project: UTAH-UINTAH Site: NBU 922-36C PAD Rig Name No: PROPETRO 12/12, ENSIGN 138/138

Event: DRILLING End Date: 3/16/2012 Start Date: 11/22/2011

Active Datum: R	KB @5,1	10.01ft (abov	e Mean Sea	Start Date	UM: NE/NW/0/9/S/22/E/36/0/0/26/PM/N/706/W/0/1749/0/0							
Level)  Date		Time art-End	Duration (hr)	Phase	Code .	Sub Code	P/U	MD From Operation;				
	10:00	- 10:30	0.50	DRLPRC	14	В	Р	PULLED THE WEAR BUSHING AND HELD A SAFETY MEETING WITH BAKER ATLAS PRIOR TO RIGGING UP.				
	10:30	- 14:00	3.50	EVALPR	11	D	P	RIGGED UP AND RAN TRIPLE COMBO LOG. DRILLERS TD 8955', LOGGERS BRIDGED OUT @ 6920'. WE LOGGED OUT TO SURFACE AS PER NICK SPENCE. NO 2ND ATTEMPT WAS MADE.				
	14:00	~ 23:00	9.00	CSGPRO	12		P	HELD A SAFETY MEETING WITH FRANKS RIGGED UP AND RAN 213 TOTAL JOINTS, (94 JTS. OF 4.5"/1-80 / 11.6# / LTC), (119 JTS. OF 4.5" / 11.6# / 1-80 / DQX). LANDED AT 8938.08, FLOAT COLLAR @ 8892.83, MV MARKER @ 6678.50, DQX CROSS OVER @ 4971.35`.				
	23:00	- 0:00	1.00	CSGPRO	05		Р	CIRCLATED THE CASING ON BOTTOM. 85 STROKES, 385 GPM,850 PSI NO FLARE ON BOTTOMS UP				
3/16/2012	0:00	- 0:30	0.50	CSGPRO	05	D	Р	CIRCLATED THE CASING ON BOTTOM. 85 STROKES, 385 GPM,850 PSI NO FLARE ON BOTTOMS UP				
	0:30	- 3:00	2.50	CSGPRO	12	E	P	DROPPED BOTTOM PLUG, PUMPED 25 BBL 8.34 WATER SPACER ,432 SX PREMIUM LITE II CEMENT + 0.5 LBS/SX STATIC FREE + 0.2% BWOC R-3 + 0.25 LBS/SX CELLO FLAKE + 5 LBS/SX KOL SEAL + 0.4% BWOC SODIUM METASILICATE + 6% BWOC BENTONITE II +.6 BWOC FL-52 + 119.7% FRESH WATER 12.0#, 2.26 YIELD LEAD CEMENT , 995 SX 50:50 POZ (ASH FLY) CLASS G + 0.005 LBS/SX STATIC FREE + 10% BWOW SODIUM CHLORIDE + 0.15% BWOC R-3 + 0.002 GPS FP-6L + 2% BENTONITE II + 58.7% FRESH WATER, DROPPED THE TOP PLUG, DISPLACE W/ 138.5 BBLS CLAYCARE + 1 GAL MAGNACIDE @ 8.34 PPG WATER , FINAL LIFT 2500 PSI, BUMPED BLUG @ 3000 PSI , FLOATS HELD,1.5 BBL. WATER BACK TO THE TRUCK, 20 BBLS OF SPACER BACK TO PIT , TOP OF TAIL EST @ 3980 ',TOP OF LEAD EST @ 115',				
	3:00	- 3:30	0.50	CSGPRO	14	В	P	PULLED THE DRILLING RUBBER AND SET 95K ON THE C-22 SLIPS.				
	3:30 5:00	- 5:00	1.50	CSGPRO	14	Α	P	NIPPLED DOWN THE BOP AND CUT OFF THE CASING				
and the second s	5:00	- 6:00	1,00	RDMO	01		P	PREPPED THE RIG FOR SKIDDING. RIG RELEASED @ 06:00				

## 1 General

#### 1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

#### 1.2 Well/Wellbore Information

UWI	NE/NW/0/9/S/22/E/36/0/0/26/PM/N/706/W/0/174	19/0/0		
Spud Date	2/4/2012	Active Datum	RKB @5,110.01ft (above Mean Sea Level)	
Start Date	4/23/2012	End Date	5/9/2012	
Rig Name/No.		Event	COMPLETION	
Project	UTAH-UINTAH	Site	NBU 922-36C PAD	
Report No.	1	Report Date	4/23/2012	
Well Name	NBU 922-36C4BS	Wellbore Name	NBU 922-36C4BS	
Well	NBU 922-36C4BS BLUE	Wellbore No.	OH	

#### 1.3 General

Contractor	CASED HOLE SOLUTIONS	Job Method	Supervisor	KEN WARREN
Perforated Assembly	PRODUCTION CASING	Conveyed Method		

#### 1.4 Initial Conditions

# 1.5 Summary

Fluid Type		Fluid Density	Gr	ross interval	7,076.0 (ft)-8,750.0 (ft)	Start Date/Time	4/23/2012 12:00AM
Surface Press		Estimate Res Press	No	o. of intervals	42	End Date/Time	4/23/2012 12:00AM
TVD Fluid Top		Fluid Head	To	otal Shots	168	Net Perforation Interval	48.00 (ft)
Hydrostatic Press		Press Difference	A	vg Shot Density	3.50 (shot/ft)	Final Surface Pressure	
Balance Cond	NEUTRAL			_		Final Press Date	

#### 2 Intervals

#### 2.1 Perforated Interval

Date Formation/ CCL@ Reservoir (ff)	CCL-T MD Top. S (ft)	(ft),		Add. Shot: r	tage No Carr Size (in)	Phasing (*)	Charge Desc /Charge Charge Reason Misrun Weight (gram)
4/23/2012 MESAVERDE/	7,076.0	7,077.0	4.00	0.360 EXP/	3.375	90.00	23.00 PRODUCTIO
12:00AM						:	. N

#### 2.1 Perforated Interval (Continued)

Date	Formation/ CCL@			Shot	Misfires/ Diamete Carr Type /Stage No	Carr	Phasing	Charge Desc/Charge	Charge	Reason	Misrun
	Reservoir (ft)	S (ft)	(ft)	Density (shot/ft)	Add. Shot r (in)	Size (in)	(°)-	Manufacturer	Weight (gram)		
	MESAVERDE/	7,104.0	7,105.0	4.00	0.360 EXP/	3.375	90.00	<u> </u>		PRODUCTIO	
12:00AM		·		گون به حد						N	· ··· - · · · - · · ·
4/23/2012 12:00AM	MESAVERDE/	7,123.0	7,124.0	4.00	0.360 EXP/	3.375	90.00		23.00	PRODUCTIO	
	MESAVERDE/	7.175.0	7.176.0	4.00	0.360 EXP/	3.375	90.00		23.00	PRODUCTIO	
12:00AM	WILOAVENDE	7,175,0	7,170.0	4.00	0.560 EAT/	0.075	30.00		20,00	N	
4/23/2012	MESAVERDE/	7,191.0	7,192.0	4.00	0.360 EXP/	3.375	90,00		23.00	PRODUCTIO	
12:00AM	· · · · · · · · · · · · · · · · · · ·									N	
	MESAVERDE/	7,254.0	7,255.0	4.00	0.360 EXP/	3.375	90.00		23.00	PRODUCTIO	
12:00AM	MESAVERDE/	7,309.0	7,310.0	4.00	0,360 EXP/	3.375	90.00		23.00	PRODUCTIO	1
12:00AM	WESAVERDE/	7,309.0	7,310.0	4.00	0.560 EAF/	3.373	30.00		25.00	N N	
	MESAVERDE/	7,337.0	7,338.0	4.00	0.360 EXP/	3.375	90.00		23.00	PRODUCTIO	:
12:00AM						<u></u>				N	
4/23/2012 12:00AM	MESAVERDE/	7,399.0	7,400.0	4.00	0.360 EXP/	3.375	90.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/	7,489.0	7,490.0	4.00	0.360 EXP/	3.375	90.00			PRODUCTIO N	:
4/23/2012 12:00AM	MESAVERDE/	7,556.0	7,558.0	4.00	0.360 EXP/	3.375	90.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/	7,622.0	7,623.0	4.00	0.360 EXP/	3.375	90.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/	7,709.0	7,710.0	4.00	0.360 EXP/	3.375	90.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/	7,805.0	7,806.0	4.00	0.360 EXP/	3.375	90.00			PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/	7,818.0	7,819.0	4.00	0.360 EXP/	3.375	90.00			PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/	7,851.0	7,853.0	4.00	0.360 EXP/	3.375	90.00		23.00	PRODUCTIO N	
	MESAVERDE/	7,903.0	7,904.0	3.00	0.360 EXP/	3.375	120.00		23.00	PRODUCTIO N	:
4/23/2012 12:00AM	MESAVERDE/	7,924.0	7,925.0	3.00	0.360 EXP/	3.375	120.00		23.00	PRODUCTIO N	
	MESAVERDE/	7,943.0	7,944.0	3.00	0.360 EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/	7,971.0	7,972.0	3.00	0.360 EXP/	3.375	120.00		23.00	PRODUCTIO N	3
and the second second	MESAVERDE/	8,004.0	8,006.0	3.00	0.360 EXP/	3.375	120.00		· · · · · · · · · · · · · · · · · · ·	PRODUCTIO N	:
A CONTRACTOR OF THE PARTY OF TH	MESAVERDE/	8,046.0	8,048.0	3.00	0.360 EXP/	3.375	120.00			PRODUCTIO N	:

#### 2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ CCL-T	MD Top	MD Base (ft)	Shot Density	Misfires/ Add. Shot	Diamete	Carr Type /Stage No	Carr Size	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight	Reason	Misrun
	Reservoir	(ft) (ft)	114		(shot/ft)	Add, Stiot	(in)		(in)	'''	Wallulaçıdı	(gram)		
4/23/2012 12:00AM	MESAVERDE/	. In the second second second second	8,093.0				0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,113.0	8,114.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/	:	8,142.0	8,143.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,160.0	8,161.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,188.0	8,189.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,206.0	8,208.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,239.0	8,240.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,292.0	8,293.0	3.00	1	0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,311.0	8,312.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	:
4/23/2012 12:00AM	MESAVERDE/		8,342.0	8,343.0	3.00	:	0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,371.0	8,372.0	3.00	: :	0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,395.0	8,396.0	3.00	:	0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,409.0	8,410.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,435.0	8,437.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,494.0	8,495.0	4.00	:	0.360	EXP/	3.375	90.00			PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,613.0	8,614.0	4.00	:	0.360	EXP/	3.375	90.00			PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,639.0	8,640.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,692.0	8,693.0	4.00		0.360	EXP/	3.375	90.00			PRODUCTIO N	
4/23/2012 12:00AM	MESAVERDE/		8,723.0	8,724.0	4.00		0,360	EXP/	3.375	90.00		23.00	PRODUCTIO N	<u> </u>
4/23/2012 12:00AM	MESAVERDE/		8,749.0	8,750.0	4.00		0.360	EXP/	3.375	90.00		23.00	PRODUCTIO N	

#### 3 Plots

# **Operation Summary Report**

 Well: NBU 922-36C4BS BLUE
 Spud Date: 2/4/2012

 Project: UTAH-UINTAH
 Site: NBU 922-36C PAD
 Rig Name No: MILES 2/2

 Event: COMPLETION
 Start Date: 4/23/2012
 End Date: 5/9/2012

Active Detum: Pl		10 01# (-1-	o Moon Son	Start Date			22/E/2	36/0/0/26/PM/N/706/W/0/1749/0/0
Active Datum: Rh Level)	\o_@3,1	10.011t (abo\	re ivicari sea	OFFICE AND A STATE OF THE STATE				
Date		Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From Operation
2/4/2012	. <del> </del>	-	,					
4/26/2012	9:30	- 11:00	1.50	SURFPR	33		Р	FILL SURFACE CSG. MIRU B&C QUICK TEST. PSI TEST T/ 1000 PSI. HELD FOR 15 MIN LOST 16 PSI.
								PSI TEST T/ 3500 PSI. HELD FOR 15 MIN LOST 27 PSI. 1ST PSI TEST T/ 7000 PSI. HELD FOR 30 MIN LOST
								59 PSI. NO COMMUNICATION OR MIGRATION WITH
								SURFACE CSG BLEED OFF PSI. SWIFN
4/27/2012	7:45	- 8:30	0.75	COMP	48		Р	HSM & JSA W/CASEDHOLE SOLUATIONS
	10:00	- 11:30	1,50	COMP	37	В	P	WHP 0 PSI. MIRU CASEDHOLE SOLUATIONS. PERF STG 1) P/U 3 1/8" EXP GNS, 23 GRM, 0.36 HOLE, 120 DEG PHSG. PERF M.V. AS PER PERF DESIGN. POOH & HANG BACK LUB. SWI – SDFN.
4/30/2012	6:30	- 7:00	0.50	COMP	48		Р	HSM & JSA W/SUPERIOR WELL SERVICE & CASEDHOLE SOLUATIONS
	7:41	- 8:08	0.45	COMP	36	Е	P	MIRU SUPERIOR WELL SERVICE. P/T SURFACE EQUIP TO 8000 PSI. LOST 75 PSI IN 5 MIN. FRAC STG 1) WHP 1256 PSI. BRK DWN PERF 5.3 BPM @ 3694 PSI. ISIP 2245 PSI. FG. 0.70. EST INJ
								RATE 50.8 BPM @ 4885 PSI. 24/24 PERFS OPEN - 100%. ((LOST RATE @ 698 BBLS IN - CAUGHT AIR FROM TRANSFER PUMP)) MP 6507 PSI, MR 51.3 BPM, AP 4095 PSI, AR 46.3
								BPM. ISIP 2521 PSI, FG. 0.73, NPI 276 PSI. PMP'D 1025 BBLS SLK WTR, 17,737 LBS 20/40 SND. X-OVER FOR WL.
	8:38	- 9:38	1.00	COMP	37	В	Р	PERF STG 2) P/U HALCO 8K CBP & 3 1/8" EXP GNS, 23 GRM, 0.36 HOLE, 90 DEG PHSG. RIH SET CBP @ 8467'. PERF MESA VERDE AS PER PERF DESIGN. POOH & HANG BACK LUB. X-OVER FOR FRAC
	9:40	- 10:08	0.47	COMP	36	E	Ρ.	FRAC STG 2) WHP 1521 PSI. BRK DWN PERF 5.1 BPM @ 2260 PSI. ISIP 1518 PSI. FG. 0.62. EST INJ RATE 50.9 BPM @ 4707 PSI. 21/24 PERFS OPEN - 81%.
								MP 5077 PSI, MR 51.1 BPM, AP 4738 PSI, AR 50.4 BPM. ISIP 2667 PSI, FG. 0.76, NPI 1149 PSI. PMP'D 939 BBLS SLK WTR, 28,985 LBS 20/40 SND. X-OVER FOR WL. ((RAN FR @ 0.25/M))
	10:13	- 11:13	1.00	COMP	37	В	Р	PERF STG 3) P/U HALCO 8K CBP & 3 1/8" EXP GNS, 23 GRM, 0.36 HOLE, 120 DEG PHSG. RIH SET CBP @ 8270'. PERF MESA VERDE AS PER PERF DESIGN. POOH & HANG BACK LUB. X-OVER FOR FRAC

# **Operation Summary Report**

 Well: NBU 922-36C4BS BLUE
 Spud Date: 2/4/2012

 Project: UTAH-UINTAH
 Site: NBU 922-36C PAD
 Rig Name No: MILES 2/2

 Event: COMPLETION
 Start Date: 4/23/2012
 End Date: 5/9/2012

Event: COMPLE	TION			Start Dat	te: 4/23/26	012		End Date: 5/9/2012
Active Datum: R Level)	KB @5,1	10.01ft (abov	e Mean Sea		UWI: N	E/NW/0/9	8/S/22/E/36/0/0/26/PM/N/7	06/W/0/1749/0/0
Date		Time art-End	Duration (hr)	Phase	Code	Sub	P/U MD From (ff)	<b>Operation</b>
		- 12:13	0.55	COMP	36	E	P	FRAC STG 3) WHP 1582 PSI. BRK DWN PERF 5 BPM @ 3110 PSI. ISIP 2449 PSI. FG. 0.74. EST INJ RATE 50.7 BPM @ 4742 PSI. 24/24 PERFS OPEN - 100%. MP 5241 PSI, MR 51.3 BPM, AP 4550 PSI, AR 50.9 BPM. ISIP 2417 PSI, FG. 0.73, NPI (-32) PSI. PMP'D 1225 BBLS SLK WTR, 28,639 LBS 20/40 SND. X-OVER FOR WL. ((RAN FR @ 0.25/M))
	12:18	- 13:18	1.00	COMP	37	В	P ·	PERF STG 4) P/U HALCO 8K CBP & 3 1/8" EXP GNS, 23 GRM, 0.36 HOLE, 120 DEG PHSG. RIH SET CBP @ 8078". PERF MESA VERDE AS PER PERF DESIGN. POOH & HANG BACK LUB. X-OVER FOR FRAC
	14:01	- 14:28	0.45	COMP	36	E	P	FRAC STG 4) WHP 1294 PSI. BRK DWN PERF 4.8 BPM @ 2773 PSI. ISIP 1794 PSI. FG. 0.66. EST INJ RATE 54.6 BPM @ 4744 PSI. 23/24 PERFS OPEN - 97%. MP 4870 PSI, MR 55.4 BPM, AP 4428 PSI, AR 54.8 BPM. ISIP 2490 PSI, FG. 0.75, NPI 696 PSI. PMP'D 1239 BBLS SLK WTR, 29,544 LBS 20/40 SND. X-OVER FOR WL. ((RAN FR @ 0.25/M))
	14:33	- 15:33	1.00	COMP	37	В	<b>p</b>	PERF STG 5) P/U HALCO 8K CBP & 3 1/8" EXP GNS, 23 GRM, 0.36 HOLE, 90 DEG PHSG. RIH SET CBP @ 7883'. PERF MESA VERDE AS PER PERF DESIGN. POOH & HANG BACK LUB. X-OVER FOR FRAC
	16:13	- 16:46	0.55	COMP	36	E	Р	FRAC STG 5) WHP 162 PSI. BRK DWN PERF 4.9 BPM @ 2498 PSI. ISIP 1392 PSI. FG. 0.62. EST INJ RATE 51 BPM @ 4225 PSI. 21/24 PERFS OPEN - 88%. MP 4445 PSI, MR 50.3 BPM, AP 3996 PSI, AR 48.9 BPM. ISIP 2297 PSI, FG. 0.74, NPI 905 PSI. PMP'D 1405 BBLS SLK WTR, 31,205 LBS 20/40 SND. X-OVER FOR WL. ((RAN FR @ 0.25/M))
	16:51	- 17:41	0.83	COMP	37	В	P	PERF STG 6) P/U HALCO 8K CBP & 3 1/8" EXP GNS, 23 GRM, 0.36 HOLE, 90 DEG PHSG. RIH SET CBP @ 7588'. PERF MESA VERDE AS PER PERF DESIGN. POOH & HANG BACK LUB. X-OVER FOR FRAC. SWI - SDFN.
5/1/2012	6:45	- 7:00	0.25	COMP	48		Р	HSM & JSA W/SUPERIOR WELL SERVICE & CASEDHOLE SOLUATIONS
	7:33	- 7:54	0.35	COMP	36	Ē	Р	FRAC STG 6) WHP 175 PSI. BRK DWN PERF 5.2 BPM @ 2125 PSI. ISIP 1515 PSI. FG. 0.64. EST INJ RATE 51.3 BPM @ 4434 PSI. 20/24 PERFS OPEN - 85%. MP 4614 PSI, MR 51.6 BPM, AP 4129 PSI, AR 51.3 BPM. ISIP 2202 PSI, FG. 0.73, NPI 687 PSI. PMP'D
	7:59	- 8:49	0.83	СОМР	37	В	Р .	917 BBLS SLK WTR, 21,604 LBS 20/40 SND. X-OVER FOR WL. ((RAN FR @ 0.25/M)) PERF STG 7) P/U HALCO 8K CBP & 3 1/8" EXP GNS, 23 GRM, 0.36 HOLE, 90 DEG PHSG. RIH SET CBP @ 7258'. PERF MESA VERDE AS PER PERF DESIGN. POOH & HANG BACK LUB. X-OVER FOR FRAC

# **Operation Summary Report**

Well: NBU 922-36C4BS BLUE Spud Date: 2/4/2012 Project: UTAH-UINTAH Site: NBU 922-36C PAD Rig Name No: MILES 2/2 Event: COMPLETION Start Date: 4/23/2012 End Date: 5/9/2012

UWI: NE/NW/0/9/S/22/E/36/0/0/26/PM/N/706/W/0/1749/0/0

ctive Datum: Rh evel)						M: NE/NW/0/9/S/22/E/36/0/0/26/PM/N/706/W/0/1749/0/0						
Date	F 750	Time art-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	<b>Operation</b>			
		- 11:07	0.62	COMP	36	E	Р	W	FRAC STG 7) WHP 180 PSI. BRK DWN PERF 5 BPM @ 2682 PSI. ISIP			
									877 PSI. FG. 0.56. EST INJ RATE 51 BPM @ 4060 PSI. 17/24 PERFS			
									OPEN - 77%.			
									MP 4358 PSI, MR 51.3 BPM, AP 4060 PSI, AR 50.7			
									BPM. ISIP 2180 PSI, FG. 0.74, NPI 1303 PSI. PMP'D 1185 BBLS SLK WTR, 29,595 LBS 20/40 SND.			
									X-OVER FOR WL. ((RAN FR @ 0.25/M)) ((HAD			
									XTRA SND - RAN 30.5% MORE SND THIS STG.))			
	11:12	- 12:12	1.00	COMP	34	ı	P		KILL PLUG) RIH W/HALCO 8K CBP & SETL @ 7026'. POOH & R/D WIRELINE & SUPERIOR. SWI - SDFN.			
									TOTAL WATER 7,934 BBLS			
									TOTAL SAND 187,309 LBS			
									SCALE INHIBITOR 173 GAL BIOCIDE 70 GAL			
5/9/2012	7:00	- 7:30	0.50	DRLOUT	48		P		RU 70 GAL			
	7:30	- 17:00	9.50	DRLOUT	44		P		MIRU, NDWH, NU BOP'S, TEST BOP'S 3000#, PU POBS ASSY,TIH TBG TAG PLUG# 1, BREAK CIRC,			
									MILL PLUGS 1-8.C/O 90' SAND, TO PBTD 8893'			
									BREAK CIRC			
									PLUG# 1 7026' 10'SAND 5 MIN 200# KICK			
									PLUG# 2 7280' 50' SAND 5 MIN 000# KICK PLUG# 3 7588' 30' SAND 5 MIN 000# KICK			
									PLUG# 4 7883' 60' SAND 5 MIN 100# KICK			
									PLUG# 5 8078' 50' SAND 5 MIN 000# KICK			
									PLUG# 6 8270' 40' SAND 5 MIN 000# KICK			
									PLUG# 7 8463' 30' SAND 5 MIN 100# KICK			
									PU TO 8250.10' LAND TBG, ND BOP'S, NUWH,			
									POBS, 2500#, TEST HARD LINE WH-SAND TRAP,			
									2500#, 15 MIN,TURN TO FBC RDMO TO 922-38F1CS TBG 260 JTS 8233.07'			
									KB 14.00'			
									HANGER .83'			
									XNSN 2.20'			
									EOT 8250.10'			
									PBTD 8893' BTM PERF 8750'			
									FRAC WTR 7934 BBLS			
									RCVD 2100 BBLS			
	17:10	- 17:40	0.50	DRLOUT	50				LTR 5834 BBLS WELL TURNED TO SALES @ 17:10 HR ON 5/9/2012-			
									900 MCFD, 1680 BWPD, FCP 1460#, FTP 1220#, 20/64"			
5/10/2012	7:00	-			50				WELL IP'D ON 5/10/12 - 1217 MCFD, 0 BOPD, 990			
					70				BWPD, CP 1400#, FTP 850#, CK 20/64, LP 118#, 24			
									HRS			

6/20/2012

9:41:04AM



Project: Uintah County, UT UTM12 Site: NBU 922-36C PAD

Well: NBU 922-36C4BS bore: OH

Wellbore: OH Design: OH



WELL DETAILS: NBU 922-36C4BS


GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138)


+N/-S +E/-W Northing Easting Latittude Longitude
0.00 0.00 14529339.39 2091108.31 39.997876 -109.390809



Azimuths to True North Magnetic North: 11.07°

> Magnetic Field Strength: 52376.9snT Dip Angle: 65.90° Date: 02/07/2011 Model: IGRF2010





#### PROJECT DETAILS: Uintah County, UT UTM12

Geodetic System: Universal Transverse Mercator (US Survey Feet)
Datum: NAD 1927 - Western US
Ellipsoid: Clarke 1866

Ellipsoid: Clarke 1866 Zone: Zone 12N (114 W to 108 W) Location: SECTION 36 T9S R22E System Datum: Mean Sea Level

Design: OH (NBU 922-36C4BS/OH)

Created By: Gabe Kendall Date: 15:05, March 28 2012



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36C PAD NBU 922-36C4BS

OH

Design: OH

# **Standard Survey Report**

28 March, 2012





# SDI

## Survey Report



Company:

Kerr McGee Oil and Gas Onshore LP

Project Site:

Uintah County, UT UTM12

Well:

NBU 922-36C PAD NBU 922-36C4BS

Wellbore: Design:

ОН

Local Co-ordinate Reference:

Well NBU 922-36C4BS

TVD Reference: MD Reference:

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138) GL 5096 & KB 14 @ 5110,00ft (ENSIGN 138)

North Reference:

Database:

True

Survey Calculation Method:

Minimum Curvature EDM 5000.1 Single User Db

Project

Uintah County, UT UTM12

Map System:

Universal Transverse Mercator (US Survey Feet)

System Datum:

Mean Sea Level

Geo Datum:

NAD 1927 - Western US

Map Zone:

Site

Well

Zone 12N (114 W to 108 W)

NBU 922-36C PAD, SECTION 36 T9S R22E Northing:

14.529.345.12 usft

39.997892

Site Position: From:

Lat/Long

Easting:

2,091,100.19 usft

Latitude: Longitude:

-109.390838

**Position Uncertainty:** 

0.00 ft

Slot Radius:

13.200 in

1.03 °

**Grid Convergence:** 

Well Position

+N/-S +E/-W 0.00 ft 0.00 ft

Northing: Easting:

14,529,339.40 usft 2,091,108,31 usft Latitude:

39.997876

**Position Uncertainty** 

0.00 ft

NBU 922-36C4BS, 706 FNL 1749 FWL

Wellhead Elevation:

ft

Longitude: **Ground Level:** 

-109,390809 5,096.00 ft

Wellbore

OH

Magnetics

**Model Name** 

OH

1.0

Sample Date

Declination (°)

Dip Angle (°)

Field Strength

(nT)

**IGRF2010** 

02/07/11

11.07

65.90

52.377

Design

**Audit Notes:** 

Version:

Phase:

ACTUAL

0.00

Tie On Depth:

0.00

0.00

Vertical Section:

Depth From (TVD) (ft)

+N/-S 0.00 +E/-W (ft)

Direction (°)

92.06

Survey Program

03/28/12

From

To Survey (Wellbore) (ft)

**Tool Name** 

Description

10.00 2,674.00 2,550.00 Survey #1 SDI MWD SURFACE (OH) 8,955.00 Survey #2 SDI MWD PRODUCTION (OH) MWD SDI MWD SDI

MWD - Standard ver 1.0.1 MWD - Standard ver 1.0.1

Measured Depth (ft)	inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (N)	Vertical Section (ft)	Dogleg Rate (*/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
10.00	0.00	0.00	10.00	0.00	0.00	0.00	0.00	0.00	0.00
187.00	0.53	209.58	187.00	-0.71	-0.40	-0.38	0.30	0.30	0.00
FIRST SDI MV	ND SURFACE S	URVEY							
273.00	1.97	103.87	272.98	-1.41	0.83	0.88	2.53	1.67	-122.92
354.00	3.34	98.75	353.89	-2.11	4.52	4.59	1.71	1.69	-6.32
444.00	5.23	94.30	443.64	-2.81	11.20	11.29	2.13	2.10	-4.94
534.00	6.82	88.73	533,14	-3.00	20.63	20.73	1.88	1.77	-6.19
624.00	8.90	85.15	622.29	-2.29	32.92	32.98	2.37	2.31	-3.98
714.00	10.46	88.47	711.00	-1.49	48.02	48.04	1.84	1.73	3.69



# **SDI** Survey Report



Company:

Kerr McGee Oil and Gas Onshore LP

Project: Site: Uintah County, UT UTM12

Site:

NBU 922-36C PAD NBU 922-36C4BS

Wellbore: Design: OH OH Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference:

Survey Calculation Method: Database:

Well NBU 922-36C4BS

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138)

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138)

True

Minimum Curvature

EDM 5000,1 Single User Db

y					9/1/4/1/4/				
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (*/190ft)	Bulld Rate (°/100ft)	Turn Rate (°/100ft)
804.00	10.99	92.60	799.43	-1.66	64.76	64.78	1.04	0.59	4.59
894.00	10,38	96.82	887.87	-3.01	81,38	81.43	1.10	-0.68	4.69
984.00	10.59	93.34	976.37	-4.45	97.68	97.78	0.74	0.23	-3.87
1,074.00	9.76	88.29	1,064.96	-4.71	113.57	113.66	1.35	-0.92	-5.61
1,164.00	9,58	92,77	1,153.68	-4.84	128.67	128.76	0.86	-0.20	4.98
1,254.00	8.71	90.40	1,242.53	-5.25	142.97	143.06	1.05	-0.97	-2.63
1,344.00	8.18	95.41	1,331.56	-5.90	156,16	156.27	1.01	-0.59	5.57
1,434.00	8.79	94.53	1,420.57	-7.05	169.39	169.53	0.69	0.68	-0.98
1,524.00	8.35	96.82	1,509.57	-8.37	182.73	182.91	0.62	-0.49	2.54
1,614.00	8.88	94.18	1,598.55	-9.65	196.15	196.37	0.73	0.59	-2,93
1,704.00	8.71	92.77	1,687.50	-10.49	209.88	210.12	0.31	-0.19	-1.57
1,794.00	8.35	94.97	1,776.50	-11.38	223.20	223.46	0.54	-0.40	2.44
1,884.00	8.27	94.44	1,865.56	-12.45	236.16	236.46	0.12	-0.09	-0.59
1,974.00	7.39	99.89	1,954.72	-13.95	248.32	248.66	1.28	-0.98	6.06
2,064.00	7.30	89.87	2,043.98	-14.93	259.74	260.11	1.43	-0.10	-11.13
2,154.00	8,00	86.01	2,133.18	-14,48	271.70	272.05	0.96	0.78	-4.29
2,244.00	8.53	86.97	2,222.25	-13.69	284.62	284,92	0.61	0.59	1.07
2,334.00	8.53	85.13	2,311.25	-12.77	297.93	298.20	0.30	0.00	-2.04
2,424.00	8.30	86.93	2,400.28	-11.86	311.07	311.29	0.39	-0.26	2.00
2,514.00	7.65	91.28	2,489.41	-11.64	323.55	323.75	0.99	-0.72	4.83
2,550.00	8.00	92.16	2,525.08	-11.79	328.44	328.66	1.03	0.97	2.44
LAST SDI M	WD SURFACE S	URVEY							
2,674.00	7.67	93.34	2,647.92	-12.60	345.33	345.56	0.30	-0.27	0.95
FIRST SDI N	IWD PRODUCTION	ON SURVEY							
2,769.00	7.21	93.02	2,742.12	-13.28	357.61	357.86	0.49	-0.48	-0.34
2,863.00	6.07	88.37	2,835.49	-13.45	368.47	368.71	1.34	-1.21	-4.95
2,958.00	5.01	95.05	2,930.04	-13.67	377.62	377.87	1.30	-1.12	7.03
3,052.00	3,43	106,03	3,023.79	-14.81	384.41	384.70	1.88	-1.68	11.68
3,147.00	1.58	100.58	3,118.69	-15.83	388,43	388.75	1.96	-1.95	-5.74
3,242.00	0.59	319.47	3,213.68	-15.70	389.40	389.72	2.18	-1.04	-148.54
3,336.00	1.38	289.10	3,307.67	-14.97	388.02	388.31	0.98	0.84	-32.31
3,431.00	1.32	275.19	3,402.64	-14.49	385,85	386.12	0.35	-0.06	-14.64
3,525.00	1.34	257.04	3,496.62	-14.64	383.70	383.98	0.45	0.02	-19.31
3,620.00	1.43	241.40	3,591.59	-15.46	381.58	381.88	0.41	0.09	-16.46
3,715.00	1.61	227.50	3,686.56	-16.93	379.55	379.91	0.43	0.19	-14.63
3,809.00	0.97	242.35	3,780.53	-18.19	377.87	378.28	0.76	-0.68	15.80
3,904.00	1.41	215.72	3,875.51	-19.51	376.48	376.94	0.73	0.46	-28.03
3,998.00	1.06	278.12	3,969.49	-20.33	374.94	375.43	1.40	-0.37	66.38
4,093.00	1.81	326.72	4,064.47	-18.95	373.25	373.69	1.44	0.79	51.16
4,187.00	1.91	18.69	4,158.42	-16.22	372.94	373,28	1.74	0.11	55.29
4,282.00	1.29	82.42	4,253.39	-14.58	374.50	374.79	1.86	-0.65	67.08
4,376.00	1.24	102.72	4,347.37	-14.67	376.54	376,83	0.48	-0.05	21.60
4,471.00	2.11	124.23	4,442.33	-15.88	378.99	379.32	1.11	0.92	22.64



# SDI Survey Report



Company:

Kerr McGee Oil and Gas Onshore LP

Project

Uintah County, UT UTM12

Site: Well: NBU 922-36C PAD NBU 922-36C4BS

Wellbore: Design:

ОН ОН Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference:

Survey Calculation Method: Database:

Well NBU 922-36C4BS

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138) GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138)

True

Minimum Curvature

EDM 5000.1 Single User Db

By				100 (100 (100 (100 (100 (100 (100 (100					
Measured Depth (ft)	inclination	Azimuth	Vertical Depth (ft)	+N/-S	+E/-W	Vertical Section (ft)	Dogleg Rate (°/190ft)	Bulld Rate (°/100ft)	Turn Rate (°/100ft)
	(9)	(9)	NO SERVICE PROPERTY	<b>(ft)</b>	<b>(ft)</b>		SWEWERS STORY		anticalise (versio
4,660.00	1.85	126.95	4,631.22	-19.67	384.31	384.77	0.15	-0.14	1.44
4,754.00	1.84	132.06	4,725.17	-21.59	386.64	387.17	0.18	-0.01	5.44
4,849.00	2.02	138.29	4,820.11	-23.86	388.89	389.49	0.29	0.19	6.56
4,944.00	0.97	165,36	4,915.08	-25.89	390.20	390.88	1.30	-1.11	28.49
5,038.00	1.14	177.49	5,009.07	-27.59	390.45	391.18	0.30	0.18	12.90
5,133.00	0.64	13.92	5,104.06	-28.02	390.62	391.37	1.86	-0.53	-172.18
5,227.00	0.79	19.46	5,198.05	-26.90	390,96	391.67	0.18	0.16	5.89
5,322.00	0.53	21.04	5,293.05	-25.87	391.33	392.01	0.27	-0.27	1.66
5,416.00	0.14	39.82	5,387.05	-25.38	391.56	392.22	0.43	-0.41	19.98
5,511.00	0.09	108,05	5,482.05	-25.31	391.71	392.36	0.14	-0.05	71.82
5,606.00	0.26	141.10	5,577.04	-25.51	391.91	392.58	0.20	0.18	34.79
5,700.00	0.58	148.46	5,671.04	-26.08	392,30	392.98	0.34	0.34	7.83
5,795.00	0.88	152.61	5,766.03	-27.13	392.88	393.61	0.32	0.32	4.37
5,889.00	1.01	161.57	5,860.02	-28.56	393.48	394.25	0.21	0.14	9.53
5,984.00	1.49	149.27	5,955.00	-30.42	394.37	395.21	0.58	0.51	-12.95
6,078.00	1.67	146,73	6,048.96	-32.61	395.75	396.67	0.21	0.19	-2.70
6,173.00	0.51	163,66	6,143.94	-34.18	396.63	397.60	1.25	-1.22	17.82
6,267.00	0.78	178.33	6,237.94	-35.22	396.77	397.77	0.33	0.29	15.61
6,362,00	0.35	203.50	6,332.93	-36,13	396.67	397,71	0,51	-0.45	26.49
6,457.00	1.46	321.46	6,427.92	-35.45	395.80	396.82	1.74	1.17	124.17
6,551.00	1.86	320.66	6,521,88	-33,33	394.09	395,03	0.43	0.43	-0.85
6,646.00	1.47	318.02	6,616.84	-31.23	392.29	393.16	0.42	-0.41	-2.78
6,740.00	1.21	310.35	6,710.82	-29.70	390.73	391.54	0.34	-0.28	-8.16
6,835.00	0.97	308.50	6,805.80	-28.55	389.34	390.11	0.26	-0.25	-1.95
6,929.00	0.55	287.14	6,899.79	-27.92	388.28	389.03	0.53	-0.45	-22.72
7,024.00	0.20	190.57	6,994.79	-27.95	387.82	388.57	0.64	-0.37	-101.65
7,118.00	0.62	139.45	7,088.79	-28.49	388.12	388.89	0.55	0.45	-54.38
7,213.00	0.95	157.19	7,183.78	-29.61	388.76	389.57	0.43	0.35	18.67
7,308.00	1.32	153.32	7,278.76	-31.31	389.55	390.43	0.40	0.39	-4.07
7,402.00	1.09	132.63	7,372.74	-32.89	390.70	391.63	0.52	-0.24	-22.01
7,498.00	0.61	107.08	7,468.73	-33.66	391.86	392,81	0.63	-0.50	-26.61
7,591.00	1.14	27.90	7,561.72	-32.98	392.76	393.69	1.28	0.57	-85.14
7,686.00	1.41	16.82	7,656.70	-31.03	393.54	394.40	0.38	0.28	-11.66
7,780.00	1.06	30.62	7,750.68	-29.17	394.32	395.11	0.49	-0.37	14.68
7,875.00	0.92	36.86	7,845.66	-27.81	395.23	395.97	0.19	-0.15	6.57
7,970.00	0.88	69.65	7,940.65	-26.94	396.37	397.08	0.54	-0.04	34.52
8,064.00	0.47	130.38	8,034.65	-26.94	397.34	398.05	0.82	-0.44	64.61
8,159.00	0.79	149.01	8,129.64	-27.76	397.97	398.71	0.40	0.34	19.61
8,253.00	1.41	144.53	8,223.62	-29.25	398.98	399.77	0.67	0.66	-4.77
8,348.00	2.01	152.36	8,318.58	-31.68	400.43	401.31	0.68	0.63	8.24
8,442.00	2.20	152.00	8,412.52	-34.73	402.04	403.03	0.20	0.20	-0.38
8,537.00	2.35	142.79	8,507.44	-37.90	404.07	405.17	0.42	0.16	-9.69
8,632.00	2.29	138.64	8,602.36	-40.87	406.51	407.71	0.19	-0.06	-4.37
8,726.00	2.37	152.44	8,696.29	-44.00	408.65	409.96	0.60	0.09	14.68



# SDI Survey Report



Company:

Kerr McGee Oil and Gas Onshore LP

**Project:** 

Uintah County, UT UTM12

Site:

NBU 922-36C PAD NBU 922-36C4BS

Well: Wellbore:

Design:

ОН ОН Local Co-ordinate Reference:

TVD Reference: MD Reference:

North Reference:

Survey Calculation Method:

Database:

Well NBU 922-36C4BS

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138)

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138)

True

Minimum Curvature

EDM 5000.1 Single User Db

Measured		100	Vertical			Vertical	Dogleg	Build	Turn
	ination	Azimuth	Depth	+N/-S	+E/-W	Section	Rate	Rate	Rate
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(%100ft)	(°/100ft)	(°/100ft)
8,821.00	3.19	156.66	8,791.17	-48.17	410.60	412.07	0.89	0.86	4.44
8,895.00	3.29	156.07	8,865.06	-52.00	412.28	413.88	0.14	0.14	-0.80
LAST SDI MWD F	RODUCTION	SURVEY							
8,955,00	3.29	156.07	8,924,96	-55.15	413.68	415.39	0.00	0.00	0.00

Design Annotations  Measured	Vertical	Local Coord	inates	
Depth (R) 187.00	Depth (ft) 187.00	+N/-S (ft) -0.71	+E/-W (ft) -0.40	Comment FIRST SDI MWD SURFACE SURVEY
2,550.00	2,525.08	-11.79	328.44	
2,674.00	2,647.92	-12.60	345.33	FIRST SDI MWD PRODUCTION SURVEY
8,895.00	8,865.06	-52.00	412.28	LAST SDI MWD PRODUCTION SURVEY
8,955.00	8,924.96	-55.15	413.68	SDI PROJECTION TO BIT

Checked By:	Approved By:	Date:



# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT UTM12 NBU 922-36C PAD NBU 922-36C4BS

OH

Design: OH

# **Survey Report - Geographic**

28 March, 2012





## SDI Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

Site: Well: NBU 922-36C PAD NBU 922-36C4BS

Wellbore: Design:

ÓН OH Local Co-ordinate Reference:

Well NBU 922-36C4BS

TVD Reference:

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138) GL 5096 & KB 14 @ 5110,00ft (ENSIGN 138)

MD Reference: North Reference:

Database:

True

Survey Calculation Method:

Minimum Curvature

EDM 5000.1 Single User Db

Project

Uintah County, UT UTM12

Map System:

Universal Transverse Mercator (US Survey Feet)

System Datum:

Mean Sea Level

Geo Datum: Map Zone:

NAD 1927 - Western US Zone 12N (114 W to 108 W)

Site

NBU 922-36C PAD, SECTION 36 T9S R22E

Site Position:

Northing:

14.529.345.12 usft

Latitude: 39.997892

From:

Lat/Long

Easting:

2,091,100.19 usft

Longitude:

-109.390838

**Position Uncertainty:** 

0.00 ff

Slot Radius:

13.200 in

**Grid Convergence:** 

1.03°

Well **Well Position**  NBU 922-36C4BS, 706 FNL 1749 FWL +N/-S

+E/-W

0.00 ft 0.00 ft

Northing: Easting:

14,529,339.40 usft 2,091,108,31 usft

11.07

Latitude:

39.997876

**Position Uncertainty** 

0.00 ft

Wellhead Elevation:

02/07/11

0.00

+N/-S

(ft)

0.00

0.00

-0.71

-1.41

-2.11

-2.81

-3.00

-2.29

-1.49

-1.66

ft

Longitude: **Ground Level:** 

-109,390809 5,096,00 ft

52 377

Wellbore

OH

Magnetics

**Model Name** 

**IGRF2010** 

Sample Date

Declination (°)

Dip Angle (°)

**Field Strength** 

92.06

(nT)

Design OH

**Audit Notes:** 

Version:

1.0

(ft)

Azimuth

(°)

0.00

0.00

209 58

103.87

98.75

94,30

88.73

85.15

88.47

92.60

Phase:

ACTUAL

Tie On Depth:

0.00

Vertical Section:

Depth From (TVD) (ft)

Date

+N/-S /ft)

0.00

+E/-W (ft)

0.00

Direction

(°)

Survey Program

From To

Inclination

(°)

0.00

0.00

0.53

FIRST SDI MWD SURFACE SURVEY

1.97

3.34

5.23

6.82

8.90

10.46

10.99

Survey (Wellbore)

**Tool Name** 

Description

2,091,129.00

2,091,141.26

2,091,156.35

2,091,173.09

10.00 2,674.00 2,550.00 Survey #1 SDI MWD SURFACE (OH)

Vertical

Depth

(ft)

03/28/12

MWD SDI

MWD - Standard ver 1.0.1 MWD - Standard ver 1.0.1

65 90

Survey

Measured

Depth

(ft)

0.00

10.00

187.00

273.00

354.00

444,00

534.00

624.00

714.00

804.00

8,955.00 Survey #2 SDI MWD PRODUCTION (OH)

0.00

10.00

187.00

272.98

353.89

443.64

533.14

622.29

711.00

799.43

MWD SDI

Map

Northina

(usft)

14,529,339.40

14,529,339.40

14,529,338.68

14,529,338.00

14,529,337.38

14,529,336,79

14,529,336.77

14,529,337.70

14,529,338.78

14,529,338.91

Map Easting (usft) Latitude Longitude -109.390809 2,091,108.31 39.997876 2,091,108.31 39.997876 -109.390809 2,091,107.92 39,997874 -109.390811 2,091,109.17 39.997872 -109.390806 39.997870 -109.390793 2,091,112.87 2,091,119.56 39.997868 -109.390769

39.997867

39.997869

39.997872

39.997871

-109,390736

-109.390692

-109.390638

-109.390578

+FI-W

(ft)

0.00

0.00

-0.40

0.83

4.52

11,20

20,63

32.92

48.02

64.76



# SDI Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project:

Uintah County, UT UTM12

Site: Well: NBU 922-36C PAD NBU 922-36C4BS

Wellbore: Design:

ОН ОН Local Co-ordinate Reference:

**TVD Reference:** MD Reference:

North Reference:

Survey Calculation Method:

Database:

Well NBU 922-36C4BS

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138)

GL 5096 & KB 14 @ 5110,00ft (ENSIGN 138)

True

Minimum Curvature

EDM 5000.1 Single User Db

urvey		graph as device weeks			Average secret for the				
Measured Depth	inclination	Azimuth	Vertical Depth	+N/-\$	+E/-W	Map Northing	Map Easting		
(ft)	(°)	n	(ft)	(ft)	(ft)	(usft)	(usft)	Latitude	Longitude
894.00	10.38	96.82	887.87	-3.01	81.38	14,529,337.86	2,091,189.73	39.997867	-109.3905
984.00	10.59	93.34	976.37	-4.45	97.68	14,529,336.71	2,091,206.06	39.997863	-109.3904
1,074.00	9.76	88.29	1,064.96	-4.71	113.57	14,529,336.74	2,091,221.94	39.997863	-109.3904
1,164.00	9.58	92.77	1,153.68	-4.84	128.67	14,529,336.88	2,091,237.05	39.997862	-109.3903
1,254.00	8.71	90.40	1,242.53	-5,25	142.97	14,529,336.73	2,091,251.35	39.997861	-109.3902
1,344.00	8.18	95,41	1,331.56	-5.90	156.16	14,529,336.32	2,091,264.55	39,997859	-109,3902
1,434.00	8.79	94.53	1,420.57	-7.05	169.39	14,529,335.41	2,091,277.80	39.997856	-109.3902
1,524.00	8.35	96.82	1,509.57	-8.37	182.73	14,529,334.33	2,091,291.16	39.997853	-109.3901
1,614.00	8.88	94.18	1,598.55	-9.65	196.15	14,529,333.29	2,091,304.60	39.997849	-109.3901
1,704.00	8.71	92,77	1,687.50	-10.49	209.88	14,529,332,70	2,091,318.35	39,997847	-109.3900
1,794.00	8.35	94.97	1,776.50	-11.38	223.20	14,529,332.05	2,091,331.68	39.997844	-109.3900
1,884.00	8.27	94.44	1,865.56	-12.45	236.16	14,529,331.22	2,091,344.66	39.997841	-109,3899
1,974.00	7.39	99.89	1,954.72	-13.95	248.32	14,529,329.94	2,091,356.84	39.997837	-109.3899
2,064.00	7.30	89.87	2,043.98	-14.93	259.74	14,529,329.16	2,091,368.27	39.997835	-109.3898
2,154.00	8.00	86.01	2,133.18	-14.48	271.70	14,529,329.83	2,091,380.23	39.997836	-109.3898
2,244.00	8.53	86.97	2,222.25	-13.69	284.62	14,529,330.85	2,091,393.13	39,997838	-109.3897
2,334.00	8.53	85.13	2,311.25	-12.77	297.93	14,529,332.01	2,091,406.42	39.997841	-109.3897
2,424.00	8.30	86.93	2,400.28	-11.86	311.07	14,529,333.16	2,091,419.54	39.997843	-109.3896
2,514.00	7.65	91.28	2,489.41	-11.64	323.55	14,529,333.60	2,091,432.01	39.997844	-109.3896
2,550.00	8.00	92.16	2,525.08	-11.79	328.44	14,529,333.54	2,091,436.91	39.997843	-109.3896
LAST SE	OI MWD SURF	ACE SURVE	Y						
2,674.00	7.67	93.34	2,647.92	-12.60	345.33	14,529,333.04	2,091,453.81	39.997841	-109,389
FIRST S	DI MWD PROI	DUCTION SU	RVEY						
2,769.00	7.21	93.02	2,742.12	-13.28	357.61	14,529,332.58	2,091,466.10	39,997839	-109.389
2,863.00	6.07	88.37	2,835.49	-13.45	368.47	14,529,332.60	2,091,476.96	39.997839	-109.389
2,958.00	5.01	95.05	2,930.04	-13.67	377.62	14,529,332.55	2,091,486.12	39.997838	-109.3894
3,052.00	3.43	106.03	3,023.79	-14.81	384.41	14,529,331.53	2,091,492.93	39.997835	-109.389
3,147.00	1.58	100.58	3,118.69	-15.83	388.43	14,529,330.58	2,091,496.97	39.997832	-109,389
3,242.00	0.59	319.47	3,213.68	-15.70	389.40	14,529,330.73	2,091,497.93	39.997833	-109.3894
3,336.00	1.38	289.10	3,307.67	-14.97	388.02	14,529,331.44	2,091,496.54	39.997835	-109.3894
3,431.00	1.32	275.19	3,402.64	-14.49	385.85	14,529,331.88	2,091,494.36	39.997836	-109.389
3,525.00	1.34	257.04	3,496.62	-14.64	383.70	14,529,331.69	2,091,492.21	39.997835	-109.389
3,620.00	1.43	241.40	3,591.59	-15.46	381.58	14,529,330.83	2,091,490.10	39,997833	-109.389
3,715.00	1.61	227.50	3,686.56	-16.93	379.55	14,529,329.33	2,091,488.10	39,997829	-109.389
3,809.00	0.97	242.35	3,780.53	-18.19	377.87	14,529,328.04	2,091,486.45	39.997826	-109.389
3,904.00	1.41	215.72	3,875.51	-19.51	376.48	14,529,326.69	2,091,485.08	39.997822	-109.389
3,998.00		278.12	3,969,49	-20.33	374.94	14,529,325.85	2,091,483.56	39.997820	-109.389
4,093.00	1.81	326,72	4,064.47	-18.95	373.25	14,529,327.19	2,091,481.84	39.997824	-109.389
4,187.00	1.91	18.69	4,158.42	-16.22	372.94	14,529,329.91	2,091,481.48	39.997831	-109.389
4,282.00	1.29	82.42	4,253.39	-14.58	374.50	14,529,331.58	2,091,483.01	39.997836	-109,389
4,376.00		102.72	4,347.37	-14.67	376.54	14,529,331.53	2,091,485.06	39.997835	-109.389
4,471.00		124.23	4,442.33	-15.88	378.99	14,529,330.37	2,091,487.53	39.997832	-109.389
4,660.00		126.95	4,631.22	-19.67	384.31	14,529,326.67	2,091,492.91	39.997822	-109.389
4,754.00		132.06	4,725.17	-21.59	386.64	14,529,324.79	2,091,495.28	39.997816	-109.389
4,849.00		138.29	4,820.11	-23,86	388.89	14,529,322.56	2,091,497.56	39.997810	-109,389
4,944.00		165.36	4,915.08	-25.89	390.20	14,529,320.56	2,091,498.92	39.997805	-109.389
5,038.00		177.49	5,009.07	-27.59	390.45	14,529,318.86	2,091,499.19	39.997800	-109.389
5,133.00		13.92	5,104.06	-28.02	390.62	14,529,318.43	2,091,499.37	39.997799	-109.389
5,227.00		19.46	5,198.05	-26.90	390.96	14,529,319.56	2,091,499.69	39,997802	-109.389
5,322.00		21.04	5,293.05	-25.87	391.33	14,529,320.59	2,091,500.05	39.997805	-109,389
5,416.00		39.82	5,387.05	-25.38	391.56	14,529,321.09	2,091,500.27	39.997806	-109.389
5,511.00		108.05	5,482.05	-25.31	391.71	14,529,321.16	2,091,500.41	39.997806	-109.389
5,606.00		141.10	5,577.04	-25.51	391.91	14,529,320.97	2,091,500.62	39.997806	-109.389
5,700.00		148.46	5,671.04	-26.08	392,30	14,529,320,41	2,091,501.01	39,997804	-109.389
5,795.00	0.88	152.61	5,766.03	-27.13	392.88	14,529,319.36	2,091,501.62	39.997801	-109,389



# SDI Survey Report - Geographic



Company:

Kerr McGee Oil and Gas Onshore LP

Project Site:

Uintah County, UT UTM12 NBU 922-36C PAD

Well:

NBU 922-36C4BS

Wellbore: Design:

ОН ОН Local Co-ordinate Reference:

TVD Reference: MD Reference;

North Reference:

Database:

Survey Calculation Method:

Well NBU 922-36C4BS

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138)

GL 5096 & KB 14 @ 5110.00ft (ENSIGN 138)

True

Minimum Curvature

EDM 5000.1 Single User Db

leasured		14.00	Vertical		tive and the second	Map	Map		
Depth	Inclination	Azimuth	Depth	+N/-S	+E/-W	Northing	Easting		
(ft)	(°)	<b>(°)</b>	(ft)	(ft)	(ft)	(usft)	(usft)	Latitude	Longitude
5,889.00	1.01	161,57	5,860.02	-28,56	393,48	14,529,317.95	2,091,502.24	39.997797	-109.3894
5,984.00	1.49	149.27	5,955.00	-30.42	394.37	14,529,316.11	2,091,503.17	39.997792	-109.3894
6,078.00	1.67	146.73	6,048.96	-32.61	395.75	14,529,313.94	2,091,504.58	39.997786	-109.3893
6,173.00	0.51	163.66	6,143.94	-34.18	396.63	14,529,312.39	2,091,505.49	39.997782	-109.3893
6,267.00	0.78	178.33	6,237.94	-35.22	396,77	14,529,311.35	2,091,505.65	39,997779	-109,3893
6,362.00	0.35	203.50	6,332.93	-36,13	396,67	14,529,310.44	2,091,505.57	39.997776	-109.3893
6,457.00	1.46	321.46	6,427.92	-35.45	395.80	14,529,311.10	2,091,504.68	39.997778	-109.3893
6,551.00	1.86	320.66	6,521.88	-33.33	394.09	14,529,313.19	2,091,502.93	39.997784	-109.3894
6,646.00	1.47	318.02	6,616.84	-31.23	392.29	14,529,315.25	2,091,501.10	39.997790	-109.3894
6,740.00	1.21	310.35	6,710.82	-29.70	390.73	14,529,316.76	2,091,499.51	39.997794	-109.389
6,835.00	0.97	308.50	6,805.80	-28.55	389.34	14,529,317.89	2,091,498.10	39.997797	-109.389
6,929.00	0.55	287.14	6,899.79	-27.92	388.28	14,529,318.50	2,091,497.03	39.997799	-109.389
7,024.00	0.20	190.57	6,994.79	-27.95	387.82	14,529,318.46	2,091,496.57	39.997799	-109.389
7,118.00	0.62	139.45	7,088.79	-28.49	388.12	14,529,317.92	2,091,496.88	39.997797	-109.389
7,213.00	0.95	157.19	7,183.78	-29,61	388.76	14,529,316.81	2,091,497.54	39.997794	-109,389
7,308.00	1.32	153.32	7,278.76	-31.31	389.55	14,529,315.12	2,091,498.36	39.997790	-109.389
7,402.00	1.09	132.63	7,372.74	-32.89	390.70	14,529,313.57	2,091,499.54	39.997785	-109.389
7,498.00	0.61	107.08	7,468.73	-33.66	391.86	14,529,312.82	2,091,500.71	39.997783	-109.389
7,591.00	1.14	27.90	7,561.72	-32.98	392.76	14,529,313.51	2,091,501.60	39.997785	-109.389
7,686.00	1.41	16.82	7,656.70	-31.03	393.54	14,529,315.48	2,091,502.35	39.997790	-109.389
7,780.00	1.06	30.62	7,750.68	-29.17	394.32	14,529,317.35	2,091,503.09	39.997796	-109.389
7,875.00	0.92	36.86	7,845.66	-27.81	395.23	14,529,318.73	2,091,503.97	39.997799	-109.389
7,970.00	0.88	69.65	7,940.65	-26.94	396.37	14,529,319.62	2,091,505.10	39.997802	-109.389
8,064.00	0.47	130.38	8,034.65	-26.94	397.34	14,529,319.64	2,091,506.07	39.997802	-109.389
8,159.00	0.79	149.01	8,129.64	-27.76	397.97	14,529,318.83	2,091,506.72	39.997799	-109.389
8,253.00	1.41	144.53	8,223.62	-29.25	398.98	14,529,317.35	2,091,507.75	39.997795	-109,389
8,348.00	2.01	152.36	8,318.58	-31.68	400,43	14,529,314.95	2,091,509,24	39.997789	-109.389
8,442.00	2,20	152.00	8,412.52	-34.73	402.04	14,529,311.93	2,091,510.91	39.997780	-109.389
8,537.00	2.35	142.79	8,507.44	-37.90	404.07	14,529,308.81	2,091,513.00	39.997772	-109.389
8,632.00	2.29	138.64	8,602.36	-40.87	406.51	14,529,305.87	2,091,515.49	39.997763	-109.389
8,726.00	2.37	152.44	8,696.29	-44.00	408,65	14,529,302.78	2,091,517.68	39.997755	-109.389
8,821.00	3.19	156.66	8,791.17	-48.17	410,60	14,529,298.65	2,091,519.71	39.997743	-109.389
8,895.00	3.29	156,07	8,865.06	-52.00	412.28	14,529,294.85	2,091,521.46	39.997733	-109.389
LAST SE	NWD PROD	UCTION SUF	RVEY						
8,955.00	3.29	156,07	8,924,96	-55,15	413.68	14,529,291,73	2,091,522,91	39,997724	-109,389

Design Annotations  Measured  Depth  (ft)	Vertical Depth (ft)	Local Coord +N/-S (ft)	inates +E/-W (ft)	Comment
187.00	187,00	-0.71	-0.40	FIRST SDI MWD SURFACE SURVEY
2,550.00	2,525.08	-11.79	328.44	LAST SDI MWD SURFACE SURVEY
2,674.00	2,647.92	-12.60	345.33	FIRST SDI MWD PRODUCTION SURVEY
8,895.00	8,865.06	-52.00	412.28	LAST SDI MWD PRODUCTION SURVEY
8,955.00	8,924.96	-55.15	413.68	SDI PROJECTION TO BIT

Checked By:	Approved By:	Date:	